

COLORADO


STATE HIGHWAY DEPARTMENT

PLAN AND PROFILE OF PROPOSED FEDERAL AID PROJECT NO. 151-A STATE HIGHWAY NO. 2 GRAND COUNTY


INDEX OF SHEETS

Sheet No.	1	2	3	4	5	6	7	8	9-20	21-56
	Plan and Profile	Plan and Profile	Plan and Profile	Plan and Profile	Plan and Profile	Plan and Profile	Plan and Profile	Plan and Profile	Plan and Profile	Cross Section Sheets

CONVENTIONAL SIGNS





SCALES
 ON PLAN, 1 IN. = 100 FT.
 ON PROFILE 1 IN. = 100 FT. HORIZONTAL
 1 IN. = 10 FT. VERTICAL
 GRADE LINE ON PROFILE IS SHOWN AS GRADE OF FINISHED ROAD
 GROSS LENGTH OF PROJECT 35183.7 FT = 6.663 MI.
 NET LENGTH OF PROJECT



Scale - 1 in. = 1 mi.

RECOMMENDED FOR APPROVAL
[Signature]
 ASSISTANT ENGINEER
 APPROVED
[Signature]
 STATE HIGHWAY ENGINEER
 RECOMMENDED FOR APPROVAL
 DIST. ENG. BUREAU PUBLIC ROADS
 RECOMMENDED FOR APPROVAL
 CHIEF ENG. BUREAU PUBLIC ROADS
 APPROVED
 DIRECTOR BUREAU PUBLIC ROADS



GENERAL NOTES

1. All timbers are to be replaced with new material.

2. All handrails are to be replaced with new material.

3. All stringers are to be replaced with new material.

4. All deck planks are to be replaced with new material.

5. All bolts and washers are to be replaced with new material.

6. All nails are to be replaced with new material.

7. All hardware is to be replaced with new material.

8. All paint is to be replaced with new material.

9. All other work is to be done as shown on the drawings.

HAIRING DIRECTIONS:

1. All timbers are to be hauled in the same direction.

2. All handrails are to be hauled in the same direction.

3. All stringers are to be hauled in the same direction.

4. All deck planks are to be hauled in the same direction.

5. All bolts and washers are to be hauled in the same direction.

6. All nails are to be hauled in the same direction.

7. All hardware is to be hauled in the same direction.


8. All paint is to be hauled in the same direction.

9. All other work is to be done as shown on the drawings.

TREATED TIMBER				
Piece	Quantity	Size	Length	Vol. Cu. Ft.
Stringers	24	12" x 12"	20'	67
Handrails	24	12" x 12"	20'	67
Deck planks	24	12" x 12"	20'	67
Stringer blocks	24	12" x 12"	20'	67
Total Treated Timber				204

UNTREATED TIMBER				
Piece	Quantity	Size	Length	Vol. Cu. Ft.
Handrails	24	12" x 12"	20'	67
Stringers	24	12" x 12"	20'	67
Deck planks	24	12" x 12"	20'	67
Stringer blocks	24	12" x 12"	20'	67
Total Untreated Timber				204

HARDWARE				
Description	Quantity	Size	Length	Weight
Bolt Handrail Posts to Piles	24	1/2"	18"	22.5
Bolt Handrail Posts to Stringers	24	1/2"	18"	22.5
Bolt Handrail Posts to Wheel Guard	24	1/2"	18"	22.5
Bolt Handrails to Posts	24	1/2"	18"	22.5
Bolt Handrails to Posts	24	1/2"	18"	22.5
Washers, 1/2" for each bolt	24	1/2"	18"	87.5
Lag Screws, 1/2" for each bolt	24	1/2"	18"	22.5
Cap Washers, Permitted only with lag screws	24	1/2"	18"	1.1
Total Weight Bolts, Washers and Lag Screws				219.5
WALTS - 2d common 16d 3d minimum 30 Lbs 40d Com. 150 Lbs				
Commoned Round Nails for Asphalt Plank 40d min 55 Lbs				



ASPHALT PLANK NOTES

1. All asphalt planks are to be replaced with new material.

2. All handrails are to be replaced with new material.

3. All stringers are to be replaced with new material.

4. All deck planks are to be replaced with new material.

5. All bolts and washers are to be replaced with new material.



6. All nails are to be replaced with new material.

7. All hardware is to be replaced with new material.

8. All paint is to be replaced with new material.

9. All other work is to be done as shown on the drawings.

SUMMARY OF QUANTITIES				
Item	Description	Unit	Quantity	Weight
1-1	Untreated Bridge Timber	3d Ft.	204	
1-2	Treated Bridge Timber	3d Ft.	204	
1-3	Asphalt Plank 1/2" thick 18" wide	Sq. Ft.	480	
1-4	Drain Pipe and Flange	Each	2	
1-5	Asphalt Plank	Sq. Ft.	600	
1-6	Asphalt Plank System & Handrails of Old Br. Lamp Sum			



COLORADO
STATE HIGHWAY DEPARTMENT
NEW FLOOR SYSTEM & HANDRAILS
FOR 21 FT. SPAN TIMBER BRIDGE


Atmos. Crooked Creek
 Sta. 515+35 to 515+42
 Near Tiber Arish, Sec. 2, T. 15, R. 16W.

Designed by EEM
 Made by HLP
 Checked by EEM

Approved by Bridge Engineer
 Date 193

GRANBY

S.E. 1/4 Sec. 31 & S.W. 1/4 Sec. 32
T. 2 N. R. 76 W.



Sta 24+51 Beginning of
F.A.P. 131-A

DENVER & SALT LAKE R.R.

Sec. 31 Sec. 32

Sta 84+51 Beginning
of F.A.P. 131-A


1-14-27

LC Enley

Structures

1-14-27

LC Enley




J. H. Chiles Jr.

Conveys all of the land situated within the Right of Way said Right of Way extending 40' on each side of the center line of the highway except where noted otherwise, said highway is located in Lots I II III of Sec. 4 T. 1 S. R. 76 W. of the 6th P.M. more particularly described as follows:-

Beginning at Sta. 437+30.7 a point on the east boundary of the Chiles property, said point is on the Sec. line and is tied to the N.E. Cor. of Sec. 4 as shown on the Map, thence N. 80° 08' W. for 1185.3', thence with a 3° curve to the left for 445.4' to Sta. 421+00, thence the R.O.W. is 40' to the left of the center line and 52' to the right, continuing on the 3° curve for 39.0', thence S. 65° 26' W. for 203.0' to Sta. 418+36, thence the R.O.W. is 52' each side of the highway S. 65° 26' W. for 12' to Sta. 418+44, thence the R.O.W. is 40' to the right and 52' to the left of the center line of the highway S. 65° 26' W. for 294.0' to Sta. 415+50, thence with an 80° R.O.W. again S. 65° 26' W. for 339.3', thence with a 7° curve to the right for 919.0', thence N. 30° 14' W. for 414.6' to Sta. 398+77.1 a point on the Base Line and north Sec. line of Sec. 4 and the north boundary line of the Chiles property said point is tied to the base line as shown on the Map.

Said R.O.W. contains 7.232 Acres of which 1.165 Acres are contained in the R.O.W. of the Old Road and 6.067 Acres are to be acquired.

The Colorado State Highway Department reserves the right to make any changes in irrigation ditches which may be necessary due to the construction of said highway. It is understood that no changes will be made in any ditches that will interfere in any way with the irrigation of the land under said ditches. The Colorado State Highway Dept. further reserves the right to construct such intercepting ditches as may be necessary for adequate drainage and protection of the road.




E. C. Pickell

Conveys all of the land situated within the Right-of-Way, said Right-of-Way extending 40' on each side of the center line of the Highway except where noted otherwise, said Highway is located in Lots II III of Sec. 3 T.1S. R.7E. of the 6th P.M. more particularly described as follows:-

Beginning at Sta. 437+30.7 a point on the west boundary of the Pickell property, said point is on the Sec. line and is tied to the N.W. Cor. of Sec. 3 as shown on the Map, thence S.80°02'E. for 669.3 feet to Sta. 444+00 thence the R.O.W. is 40' to the right of the center line and 52' to the left, S.80°02'E. for 710' to Sta. 451+10, thence with a 60' R.O.W. again S.80°02'E. for 643.2', thence with a 2° curve to the L. for 320.6 feet, thence S.86°25'E. for 373.0' to Sta. 464+47 a point on the N. + S. 1/4 line of S. 3 and the east boundary line of the Pickell property.

Said R.O.W. contains 5.184 Acres of which .789 Acres are contained in the R.O.W. of the Old Road and 4.395 Acres are to be acquired.

The Colorado State Highway Department reserves the right to make any changes in Irrigation ditches which may be necessary due to the construction of said highway. It is understood that no changes will be made in any ditches that will interfere in any way with the irrigation of the land under said ditches. The Colorado State Highway Dept. further reserves the right to construct such intercepting ditches as may be necessary for adequate drainage and protection of the road.



O. Alton Bralin

Conveys all of the land situated within the Right-of-Way, said Right-of-Way extending 40' on each side of the center line of the Highway except where noted otherwise said highway is located in Lots I and II of the N.E. 1/4 of Sec. 3 T.1S. R. 76 W. of the 6th P.M. more particularly described as follows:-

Beginning at Sta. 464+47 a point on the N. & S. 1/4 line of Sec. 3 and the west boundary of the Bralin property, said point is tied to the N. 1/4 Cor. of Sec. 3 as shown on the Map, thence S. 86° 21' E. for 822.0', thence with a 1" curve to the right for 113.3', thence S. 85° 19' E. for 282.7' to Sta. 476+65, thence the R.O.W. is 40' to the left of the center line and 52' to the right S. 85° 19' E. for 350.0' to Sta. 480+15, thence with an 80' R.O.W. again S. 85° 19' E. for 613.0' to Sta. 486+28 a point on the south lot line of Lot I & II of Sec. 3 and the south boundary of the Bralin property.

Said R.O.W. contains 4.101 Acres of which 3.004 Acres are contained in the R.O.W. of the Old Road and 1.097 Acres are to be acquired.

The Colorado State Highway Department reserves the right to make any changes in irrigation ditches which may be necessary due to the construction of said highway. It is understood that no changes will be made in any ditches that will interfere in any way with the irrigation of the land under said ditches. The Colorado State Highway Dept. further reserves the right to construct such intercepting ditches as may be necessary for adequate drainage and protection of the road.

T.1S. R.76 W. Sec. 3
W.A. Matteson Lot VIII

T.1S. R.76 W. Sec. 2
W.A. Matteson Lots I, II, III

PC 496+92.1 Δ 4°06' L.
D 2°
T 102.5'
L 203.0'
R 2065.0'

PT 499+02.1

Buck Fence

Small Creek

Buck Fence

PI 497+99.6

Buck Fence

Sta. 508+10

Sta. 511+11


W. A. Matteson

Conveys all of the land situated within the Right-of-Way said Right-of-Way extending 40' on each side of the center line of the Highway, said Highway is located in Lots I, II, III of Sec. 2 and Lot VIII of Sec. 3 T.1S. R.76 W. of the 6th P.M. more particularly described as follows:-

Beginning at Sta. 531+11 a point on the east Boundary of the Matteson property said point is tied to the North 1/4 Cor. of Sec. 2 as shown on the Map, thence N. 89°25' W. for 3208.9' thence with a 2° curve to the R. for 205.0' thence N. 85°19' W. for 1069.1' to Sta. 486+28 a point on the north Lot line of Lot No. VIII Sec. 3 and the north boundary of the Matteson property.

Said R.O.W. contains 8.233 Acres of which 6.174 Acres are contained in the R.O.W. of the Old Road and 2.059 Acres are to be acquired.

The Colorado State Highway Department reserves the right to make any changes in irrigation ditches which may be necessary due to the construction of said highway. It is understood that no changes will be made in any ditches that will interfere in any way with the irrigation of the land under said ditches. The Colorado State Highway Dept. further reserves the right to construct such intercepting ditches as may be necessary for adequate drainage and protection of the road.



Thos. Toyrien

Conveys all of the land situated within the Right of Way and Right of Easement containing 40' on each side of the center line of the Highway said highway is located in Lot VIII of the N.E. 1/4 of Sec. 2, T. 1 S., R. 76 W. of the 6th P.M. more particularly described as follows:-


Beginning at Sta. 531+11 a point on the lot line and the west boundary of the Toyrien property said point is tied to the N. 1/4 Cor. of Sec. 2 as shown on the map, thence S. 69°25'E. for 330.6, thence with a 2°30' curve to the right for 628.6', thence S. 68°42'E. for 206.6' to Sta. 545+37 a point on the east N. 1/4 Sec. line of Sec. 2 and the east boundary of the Toyrien property.

Said R.O.W. contains 2.618 Acres of which 1.949 Acres are contained in the R.O.W. of the Old Road and .669 Acres are to be acquired.

The Colorado State Highway Department reserves the right to make any changes in irrigation ditches which may be necessary due to the construction of said highway. It is understood that no changes will be made in any ditches that will interfere in any way with the irrigation of the land under said ditches. The Colorado State Highway Dept. further reserves the right to construct such intercepting ditches as may be necessary for adequate drainage and protection of the road.

Jas. Fee and Wife
W. 1/2 of S.W. 1/4 Sec. 33 E. 1/2 of S.E. 1/4 Sec. 32


Jas. Fee and Wife
Conveys all of the land situated within the Right-of-Way said Right-of-Way extending 40' on each side of the center line of the Highway except where noted otherwise said Highway is located in the W. 1/2 of the S.W. 1/4 of Sec. 33 and the E. 1/2 of the S.E. 1/4 of Sec. 32 T. 1 N. R. 76 W. of the 6th P.M. more particularly described as follows:-
The following description is tied to the S. 1/4 Cor of Sec. 33 at P.I. 361+25.0 as shown on the Map.
Beginning at Sta. 340+30 a point on the E.W. 1/4 line of Sec. 32 the R.O.W. is 40' left and 50' right of the center line thence S. 43° 43' E. for 220' to Sta. 342+70, thence the R.O.W. is 40' right and 40' left of the center line S. 43° 43' E. for 189.4' thence with a 2° curve to the L. for 41.7' thence S. 32° 33' E. for 1004.9' thence with a 4° curve to the L. for 434.6' thence S. 69° 56' E. for 391.4' to Sta. 367+32 a point on a 1/4 line of Sec. 32.
Said R.O.W. contains 4.376 Acres of which .848 Acres are contained in the R.O.W. of the Old Road and 4.128 Acres are to be acquired.
The Colorado State Highway Department reserves the right to make any changes in Irrigation ditches which may be necessary due to the construction of said highway. It is understood that no changes will be made in any ditches that will interfere in any way with the irrigation of the land under said ditches. The Colorado State Highway Dept. further reserves the right to construct such intercepting ditches as may be necessary for adequate drainage and protection of the road.




Jas. Fee and Wife
S.E. $\frac{1}{4}$ and E $\frac{1}{2}$ of S.W. $\frac{1}{4}$ of Sec. 33 T.1N. R. 76W.


Jas. Fee and Wife

Conveys all of the land situated within the Right-of-Way said Right-of-Way extending 40' on each side of the center line of the Highway, said Highway is located in the S.E. $\frac{1}{4}$ and E. $\frac{1}{2}$ of Sec. 33, T.1N. R. 76W. of the 6th P.M. more particularly described as follows:—
Beginning at Sta 398+77.1 said Sta. is tied to the South $\frac{1}{2}$ Cor. of Sec. 33 as shown on the Map, thence thence N. 30° 14' W. for 123.7' thence with a 5° curve to the L. for 1064.0 feet, thence N. 63° 26' W. for 1173.2 feet, thence with a 4° curve to the R. for 337.5 feet, thence N. 63° 56' W. for 444.7 feet, to Sta. 367+32 a point on a $\frac{1}{2}$ Sec. line of Sec. 33
Said R.O.W. contains 3.776 Acres of which 2.167 Acres are contained in the R.O.W. of the Old Road and 3.603 Acres are to be acquired.
The Colorado State Highway Department reserves the right to make any changes in Irrigation ditches which may be necessary due to the construction of said highway. It is understood that no changes will be made in any ditches that will interfere in any way with the irrigation of the land under said ditches. The Colorado State Highway Dept. further reserves the right to construct such intercepting ditches as may be necessary for adequate drainage and protection of the road.





Caroline Pippert
NE 1/4 Sec. 31, W 1/2 of NW 1/4 Sec. 32, T.1N. R.76W.



Caroline Pippert


Conveys all of the land situated within the Right-of-Way said Right-of-Way extending 40' on each side of the center line of the Highway except where noted otherwise, said highway is located in the NE 1/4 of Sec. 31 and the W 1/2 of the NW 1/4 of Sec. 32, T.1N. R.76W. 6th P.M. more particularly described as follows:-
The following description is tied to the N.W. Cor. of Sec. 32 at P.I. 293+51.7 as shown on the Map.

Beginning at Sta. 301+22 a point on a 1/4 line of Sec. 32 and the east boundary of the Pippert property, thence with the R.O.W. 40' to the left and 80' to the right of the center line N. 64°55' W. for 188' to Sta. 300, thence the R.O.W. is 40' each side of the center line N. 64°55' W. for 30.6 feet, thence with a 5° curve to the left for 420.1', thence with a 5° curve to the left for 401.1', thence S. 69°59' W. for 35.3', thence with a 8° curve to the right for 390.0', thence N. 75°43' W. for 22.3 feet to Sta. 287+00, thence the R.O.W. is 40' to the right and 52' to the left of the center line N. 75°43' W. for 200' to Sta. 285+00 thence the R.O.W. is 40' each side of the center line N. 75°43' W. for 100' to Sta. 284+00 thence the R.O.W. is 40' to the right and 52' to the left of the center line N. 75°43' W. for 150' to Sta. 282+50, thence the R.O.W. is 40' each side of the center line N. 75°43' W. for 343.3', thence with a 7° curve to the right for 306.7' to Sta. 276+00 thence the R.O.W. is 40' to the right and 52' to the left of the center line continuing on the 7° curve to the right for 150' to Sta. 274+50, thence the R.O.W. is 40' to the right and 45' to the left of the center line, continuing on the 7° curve to the right for 15' to Sta. 274+35 a point on the north Sec. line of Sec. 31 and the north boundary of the Pippert Property.

Said R.O.W. contains 5.331 Acres of which 1.874 Acres are contained in the R.O.W. of the Old Road and 3.517 Acres are to be acquired.


The Colorado State Highway Department reserves the right to make any changes in irrigation ditches which may be necessary due to the construction of said highway. It is understood that no changes will be made in any ditches that will interfere in any way with the irrigation of the land under said ditches. The Colorado State Highway Dept. further reserves the right to construct such intercepting ditches as may be necessary for adequate drainage and protection of the road.

J.F. & E. Fee
Conveys all of the land situated within the Right-of-Way said Right-of-Way extending 40 feet on each side of the center line of the Highway, said Highway is located in the N.W. 1/4 of S.E. 1/4 and N.E. 1/4 of the S.W. 1/4 and S.E. 1/4 of N.W. 1/4 of Sec. 30, T.1N. R.76W. of the 6th P.M. more particularly described as follows:-
Beginning at Sta 259+70 a point on the South E.W. 1/4 Sec. line of Sec. 30 said point is tied to the S.E. Cor. of Sec. 30 as shown on the Map, thence N. 26° 44' W. for 403.4', thence with a 4° curve to the R. for 864.2', thence N. 7° 40' W. for 1426.6' to Sta. 232+80 a point on the North E.W. 1/4 Sec. line of Sec. 30.
Said R.O.W. contains 4.948 Acres of which 0.119 Acres are contained in the R.O.W. of the Old Road and 4.829 Acres are to be acquired.
The Colorado State Highway Department reserves the right to make any changes in irrigation ditches which may be necessary due to the construction of said highway. It is understood that no changes will be made in any ditches that will interfere in any way with the irrigation of the land under said ditches. The Colorado State Highway Dept. further reserves the right to construct such intercepting ditches as may be necessary for adequate drainage and protection of the road.





Scale 1"=100'



Heirs of J.M. Tryon.
SW 1/4 of SE 1/4 Sec 18
T15S, R75W

BEING of J.M. Tryon


Whereby all of the land situated within the right-of-way, said right-of-way extends 50-ft. on each side of the highway, said highway is located in the SW 1/4 of SE 1/4 of Sec. 18, T15S, R75W, of the 6th Principal Meridian, more particularly described as follows:

Beginning at Sta. 20+70, a point on the south section line of Sec. 18, whence the S.E. section corner of Sec. 18 bears East, 1997.0-ft.; thence, along the section line, east, for 50.9-ft.; thence on a curve to the right with a radius of 188.4-ft. for 104.9-ft.; thence, along the 1/16 line, for 1064.0-ft. to a point on a 1/16 line of Sec. 18; thence, along the 1/16 line, west, for 103.6-ft.; thence, along the 1/16 line, for 1091.4-ft.; thence on a curve to the left with a radius of 188.4-ft. for 104.9-ft. to a point on the south section line of Sec. 18; thence, along the section line, East, for 50.9-ft. to the point of beginning.

Said right-of-way contains 3.125 acres, of which 1.044 acres are contained within the right-of-way of the old road, and of which 2.081 acres are to be acquired.

* center-line of the

NE 1/4 Sec 19
T15S, R75W




Cent. S. B. T. Co.

Conveys all of the land situated within the Right-of-Way said Right-of-Way extending 40 feet on each side of the center line of the highway said highway is located in the N.E. 1/4 of N.W. 1/4 of Sec. 30 and the E. 1/4 of S.W. 1/4 of Sec. 19 T. 1 N. R. 76 W. of the 6th P.M. more particularly described as follows—
The following description is tied to the S.E. Cor. of Sec. 19 at P.O.T. 210+90.3 as shown on the Map.

Beginning at Sta. 232+80 a point on the north E. & W. 1/4 line of Sec. 30 thence N. 7° 40' E. for 2480.0 feet to Sta. 208+00, thence returning to a point 40 feet right of P.C. 0+00 on Z line, thence with a boundary description, thence on a curve to the right with a 103.3' radii for 162.26', thence N. 82° 20' W. for 325.0 feet, thence S. 7° 40' W. for 80' thence S. 62° 20' E. for 325.0 feet, thence on a curve to the right with a 103.3' radii for 162.26' thence N. 7° 40' E. for 286.6 feet to the point of beginning.

Said R.O.W. contains 4.709 Acres of which 0.303 Acres are contained in the R.O.W. of the Old Road and 4.406 Acres are to be acquired.

The Colorado State Highway Department reserves the right to make any changes in Irrigation ditches which may be necessary due to the construction of said highway. It is understood that no changes will be made in any ditches that will interfere in any way with the irrigation of the land under said ditches. The Colorado State Highway Dept. further reserves the right to construct such interfering ditches as may be necessary for adequate drainage and protection of the road.



VH Lininger,
Clara P Lininger,
Alfred M Lininger,
JC Hardman,
All of that part of Sec 18 lying
East of the D & S L RR, except
SE 1/4 of SW 1/4 of Sec 18,
T. 15S, R. 75W

CLARA P. LININGER
V. H. LININGER
ALFRED M. LININGER
J. C. HARDMAN


Convey all of the land situated within the Right-of-Way, said Right-of-Way extends 50-ft. on each side of the center-line of the highway, said highway is located in that part lying east of the Denver and Salt Lake R.R. Right-of-Way, of Sec 18, except the 1/4 of S.E. 1/4, T. 15S., R. 75W. of the th. Principal Meridian; more particularly described as follows:

Beginning at Sta. 77+42, a point on the north section line of Sec. 18, whence the north & corner of Sec. 18 bears: N. 39° 39' E. 378.0-ft.; thence along the section line, N. 89° 39' E. for 51.8-ft.; thence S. 15° 18' E. for 4101.0-ft.; to a point on a 1/16 line of Sec. 18; thence, along the 1/16 line, west for 103.4-ft.; thence N. 15° 18' E. for 4100.4-ft. to a point on the north section line of Sec. 18; thence, along the section line, N. 39° 39' E. for 51.8-ft. to the point of beginning.


Said Right-of-Way contains 7.414 acres, all of which is to be acquired.


Scale: 1"=100'

NW 1/4 Sec 18
T. 15S, R. 75W



Colorado State Highway Department
Federal Aid Project No. 151-A
Right-of-Way Map No. 11





Beginning at Sta. 1139.0, a point on the north 1/16 line of sec. 7, whence a bearing survey is to corner bearing S. 4. 1/2° E. 40.0 ft. thence along said 1/16 line, S. 85° 40' E. 17.1-5 ft; thence N. 15° 13' E. for 2117.3 ft; thence on a curve to the right with a radius of 2315.0 ft for 47.4 ft; thence S. 85° 40' E. for 13.2 ft to a point on the south 1/16 line of sec. 6; thence, along said 1/16 line, S. 85° 40' E. 17.1-5 ft; thence on the east boundary line of the Section 1/16 line S. 85° 40' E. 17.1-5 ft; thence, along said 1/16 line, S. 85° 40' E. 17.1-5 ft; thence, along said 1/16 line of sec. 7, S. 15° 13' E. for 2390.4 ft to a point on the north 1/16 line of sec. 7; thence, along said 1/16 line, S. 85° 40' E. for 511.9 ft to the point of beginning.

Said right-of-way contains 6.781 acres, all of which is to be acquired.

Colorado State Highway Department
Federal Aid Project No. 151 A
Right-of-Way Map No. 12

ED Lemmon
R Van Horn
F L Earle
A B Pace
Alice B Fry
SS Hartzell
N 1/4 of NW 1/4 of Sec 2 and
SW 1/4 of SW 1/4 of Sec 6
T1S, R75W


Scale: 1 in = 100 ft.


V. D. LEXMON
A. VAN HORN
E. L. EARLE
A. B. PACE
ALICE B. FRY
S. S. HARTZELL

Convey all of the land situated within the right-of-way, said Right-of-way extends 50.0-ft. on each side of the center-line of the highway, said highway is located in the N. 1/4 of S.W. 1/4 of Sec. 7, and the S. W. 1/4 of S.W. 1/4 of Sec. 6, T. 1S., R. 75W. of the 6th principal Meridian; more particularly described as follows:

Beginning at Sta. 110+50, a point on the North 1/16 line of Sec. 7, whence M. L. & L. Survey 1/16 corner bears: 3.89° 40' E. - 1429.0-ft.; thence, along the 1/16 line, S. 89° 40' E. for 51.9-ft.; thence S. 15° 16' W. for 2361.6-ft. to a point on the South 1/16 line of Sec. 6; thence, along the 1/16 line, S. 89° 59' W. for 103.6-ft.; thence S. 15° 16' E. for 2361.4-ft. to a point on the N. 1/16 line of Sec. 7; thence, along the 1/16 line, S. 89° 40' E. for 51.9-ft. to the point of beginning.

Said right-of-way contains 6.38 acres, all of which are to be required.






Frontier Trust Co.

Conveys all of the land situated within the Right-of-Way said Right-of-Way extending 40 feet on each side of the center line of the highway said highway is located in the N.W. 1/4 of the N.W. 1/4 of Sec. 1 T. 1 S. R. 76 W. of the 6th P.M. more particularly described as follows:—

Beginning at Sta. 545+37 a point on the west Sec. line of Sec. 1 and said point tied to the N.W. Cor. Sec. 1 as shown on the Map, thence S. 68° 42' E. for 513.0 feet to Sta. 550+50 the End of F.A.P. 151-A.

Said R.O.W. contains 0.942 Acres of which 0.706 Acres are contained in the R.O.W. of the Old Road and 0.236 Acres are to be acquired.

The Colorado State Highway Department reserves the right to make any changes in Irrigation ditches which may be necessary due to the construction of said highway. It is understood that no changes will be made in any ditches that will interfere in any way with the irrigation of the land under said ditches. The Colorado State Highway Dept. further reserves the right to construct such intercepting ditches as may be necessary for adequate drainage and protection of the road.



Convey all of the land situated within the right-of-way, said right-of-way extends 40.0-ft. on each side of the center line of the highway, said highway is located in the NW 1/4 of the NW 1/4 of Sec. 1, T.1S, R.76W. of the 6th principal meridian; more particularly described as follows:

Beginning at Sta. 545+37, a point on the west section line of Sec. 1, 633.0-ft. S. 68°50' W. of P. I. 212+94.9, which P. I. is tied to the north corner of said as shown on the Map. Thence north for 42.0-ft.; thence S. 68°50' E. for 900.0-ft.; thence on a curve to the left with a radius of 1392.5-ft. for 71.1-ft.; thence south for 10.0-ft.; thence west for 120.0-ft.; thence south 400.0-ft.; thence N. 68°50' W. for 330.0-ft.; thence north for 41.0-ft. to the point of beginning.

Said right-of-way contains 1.60 acres, of which 1.000 acres are contained within the right-of-way of the old road, and of which .607 acres is to be acquired.



W.E. Fenstermacher
A.H. Keeney
Haddie Ballard
W. Ballard
All of the S 1/2 of Sec 7 lying E of D & S L. R.R.
S 1/2 of NW 1/4 Sec 7


Scale: 1 in. = 100 ft.

W. E. FENSTERMACHER
A. H. KEENEY
HADDIE BALLARD
W. BALLARD

Convey all of the land situated within the right-of-way, said right-of-way extends 50.0-ft. on each side of the center-line of the Highway, said Highway is located in that part of the S 1/2 of Sec. 7, and the S 1/2 of R. 15 E of Sec. 7, lying East of the right-of-way of the Denver & Salt Lake R. R., in T. 18 N., R. 75 W., of the 6th Principal Meridian; more particularly described as follows:

Beginning at Sta. 77+42, a point on the South section line of Sec. 7, thence the South 1/2 corner of Sec. 7, thence N. 89° 39' E. for 51.8-ft.; thence S. 15° 18' W. for 4107.4-ft. to a point on a 1/16 line of Sec. 7, whence S. 15° 18' W. for 103.3-ft. to a point on the 1/16 line of Sec. 7, whence S. 15° 18' W. for 4103.6-ft. to a point on the South section line of Sec. 7; thence, along the section line, N. 89° 39' E. for 51.8-ft. to the point of beginning.

Said right-of-way contains 9.431 acres, all of which are to be acquired.




SE 1/4 Sec 7 T. 18 N., R. 75 W.
Section Line

H. F. VOLSAMOTT
J. S. DARRETT

Convey all of the land situated within the right-of-way, said right-of-way extends 50.0-ft on each side of the center line of the Highway, except where otherwise noted, said Highway is located in the N. 1/2 of Sec. 1, T. 13S., R. 76W. of the 6th Principal meridian; more particularly described as follows:

Beginning at Sta. 198+20, a point on the north and south 1/2 line of Sec. 1, thence the N. 1/2 corner bears: North- 1335.0-ft; thence, along the 1/2 line, north for 15.0-ft to a point on the north 1/16 line of Sec. 1; thence, along the 1/16 line, east, for 154.0-ft; thence N. 76° 45' W. for 427.0-ft; thence S. 13° 15' W. for 20.0-ft; thence N. 76° 45' W. for 21.4-ft to a point on the east property line of block 4 of the town of Tabernash; thence, along said property line, south for 41.6-ft; thence S. 76° 45' E. for 16.9-ft; thence S. 13° 15' W. for 20.0-ft; thence S. 76° 45' E. for 291.1-ft to a point on the north and south 1/2 line of Sec. 1; thence, along said 1/2 line, north, for 51.4-ft. to the point of beginning.

Said right-of-way contains 0.740 acres, of which 0.106 acres are contained within the right-of-way of the old road, and of which 0.634 acres are to be acquired.



N

Scale: 1 in. = 100 ft.


U. S. HINDS

Conveys all of the land situated within the right-of-way, said right-of-way extends 40.0-ft on each side of the center line of the highway, except as otherwise noted, said highway is located in the Lots 13, 14, 415, Block 5, and Lots 1, 2, 3, & 4, Block 6, Town of Tabernash, in the N.W. 1/4 of Sec. 1, T. 13S., R. 76W., of the 6th Principal Meridian; more particularly described as follows:

Beginning at Sta. 204+54.7, a point on the west line of the alley of Block 5 167.0-ft south of the south line of Main St., said point is 531.7-ft N. 76° 45' W. of Sta. 198+20, which station is tied to the N.E. corner of Sec. 1 as shown on the map; thence, along said alley line, south for 33.0-ft to the S.E. corner of lot 13; thence, along the south line of lot 13, west for 55.0-ft; thence N. 13° 15' E. for 7.0-ft; thence N. 76° 45' W. for 73.7-ft to a point on the east property line of 2nd St.; thence, along the said east property line, north for 32.0-ft; thence, S. 76° 45' E. for 123.4-ft to a point on the west line of the alley of Block 6; thence, along said alley line, south for 41.1-ft to the point of beginning.

Beginning at Sta. 206+44.7, a point on the west property line of 2nd St. 124.0-ft south of the N.E. corner of Block 6, said point is 824.7-ft N. 76° 45' E. of Sta. 198+20, which station is tied to the N.E. corner of Sec. 1 as shown on the map; thence, along the said property line, north for 41.1-ft; thence N. 76° 45' W. for 123.4-ft to a point on the east line of the alley of Block 6; thence, along said alley line, south for 32.2-ft; thence, S. 76° 45' E. for 123.4-ft to a point on the west property line of 2nd St.; thence, along said property line, north for 41.1-ft to the point of beginning.

Said right-of-way contains 30,649.0-sq. ft. or 0.704 acres, all of which is to be acquired.






Scale: 1"=100 ft.


L. P. HINDS

Conveys all of the land situated within the Right-of-way, said Right-of-way extends 40.0-ft on each side of the center line of the Highway, except as otherwise noted, said highway is located in Lots 3, & 4, block 5, Town of Tabernash, in the N. 1/4 of Sec. 1, T. 13S., R. 76W. of the 6th Principal Meridian; more particularly described as follows:

Beginning at Sta. 203+14.0, a point on the west property line of 1st St. 201.7-ft north of the S.E. corner of Block 5, and 434.0-ft N. 76° 45' W. of Sta. 198+20, which station is tied to the north 1/2 corner of Sec. 1 as shown on the map; thence, along the said property line, north for 41.1-ft; thence N. 76° 45' W. for 128.4-ft to the west line of the alley of Block 5; thence, along said alley line, south for 72.4-ft; thence along the south line of 1st St., east for 125.3-ft. to a point on the west property line of 1st St.; thence, along said property line, north for 1.9-ft to the point of beginning.

Said Right-of-way contains 7212.5 sq. ft., or 0.166 acres, all of which is to be acquired.






School Land

Conveys all of the land situated within the right-of-way, said right-of-way extends 40.0-ft on each side of the center line of the Highway, said highway is located in Lots 14, & 15, Block 6, Town of Tabernash, Co. of Sec. 1, T.13S., R.76W. of the 6th Principal Meridian; more particularly described as follows:


Beginning at Sta. 209+13.2, a point on the east property line of 3rd St., 7.0-ft south of the N.E. corner of Block 6, and 1093.3-ft N. 76° 45' W. of Sta. 198+20, which station is tied to the N.E. corner of Sec. 1 as shown on the map; thence, along said property line, north for 2.0-ft; thence east for 125.0-ft to a point on the west line of the alley of Block 6; thence, along said alley line, south, for 78.2-ft; thence S. 7° 45' W. for 122.4-ft to a point on the east property line of 3rd St.; thence, along the said property line north for 41.1-ft, the point of beginning.

Said right-of-way contains 7762.5 sq. ft., or 0.183 acres, all of which is to be acquired.



Scale: 1in=100ft

NW 1/4 of Sec 1
T1S, R76W



Convey all of the land situated within the right-of-way, said right-of-way extends 40.0-ft on each side of the center line of the highway, except where otherwise noted, said highway is located in Lots 5, 6, & 7, block 4, and Lots 5, 6, & 12, block 5, Town of Tabernash, in the NW 1/4 of Sec. 1, T. 1S., R. 76W., of the 6th Principal Meridian; more particularly described as follows:

Beginning at Sta. 201+24, a point on the east property line of block 4, 158.0-ft north of the S.E. corner of block 4, said point is 204.0-ft N. 76° 45' W. of Sta. 198+20, which station is tied to the N.E. corner of Sec. 1 as shown on the map; thence, along said east property line, north for 41.1-ft; thence N. 76° 45' W. for 2.2-ft to the north line of lot 5; thence, along said north lot line, west for 122.3-ft to a point on the east property line of lot 5; thence, along said east property line, south for 115.0-ft; thence, S. 76° 45' E. for 127.4-ft to a point on the east property line of block 4; thence, along said east property line north, for 102.8-ft to the point of beginning.

Beginning at Sta. 203+14, a point on the west property line of lot 5, 201.0-ft north of the S.E. corner of block 5, said point is 494.0-ft N. 76° 45' W. of Sta. 198+20, which station is tied to the N.E. corner of Sec. 1 as shown on the map; thence, along said west property line, south for 1.0-ft to the N.W. corner of lot 5; thence, along the north line of lot 5, west for 125.0-ft to a point on the east line of the alley of block 5; thence, along said alley line, south for 71.5-ft; thence S. 76° 45' E. for 134.4-ft to a point on the east property line of lot 5; thence, along said west property line, north for 100.0-ft to the point of beginning.

Beginning at Sta. 204+54.7, a point on the west line of the alley of block 5, 177.0-ft south of the south line of lot 5, said point is 674.7-ft N. 76° 45' W. of Sta. 198+20, which station is tied to the N.E. corner of Sec. 1; thence, along the said alley line, south for 55.0-ft to the S.E. corner of lot 12; thence, along the north line of lot 12, west for 150.0-ft; thence S. 15° 15' W. for 53.0-ft; thence, along the south line of lot 12, east for 72.2-ft to a point on the west line of the alley of block 5; thence, along the said alley line, north for 20.0-ft to the S.E. corner of lot 12, the point of beginning.

Said right-of-way contains 30.1560-ac-ft, or 0.6924-acres, all of which is to be acquired.

NW 1/4 of Sec 1
T1S, R.76W.

A. E. ZAKS

Beginning at Sta. 102+24.4, a point on the east property line of lot St. 177.3-ft north of the S.W. corner of block 4, said point is 432.4 ft. east of Sta. 102+24.4. Station is tied to the S.W. corner of said lot as shown on the plan. thence along the said property line, north for 122.2-ft. to the S.W. corner of lot 4; thence, along the south lot line, east for 122.3-ft. thence, along 76°15'N. for 126.2-ft. to a point on the east property line of lot St.; thence, along said property line, south for 24.9-ft. to the S.W. corner of lot 4, the point of beginning.

Said right-of-way contains 1774.5-sq.ft., or 0.041 acres, all of which is to be acquired.

TABERNASH


Scale: 1 in. = 100 ft.

N. 76° 45' W.
T. 15, R. 76 W.

Conveys all of the land situated within the right-of-way, said right-of-way extends 25.0-ft on each side of the center line of the Highway, except as otherwise noted, said Highway is located in Lot 11, block 5, Town of Tabernash, in the N.W. 1/4 of Sec. 1, T. 15, R. 76 W. of the 6th principal Meridian; more particularly described as follows:

Beginning at Sta. 204+54.7, a point on the west line of the alley of block 5, 107.0-ft south of the south line of Main St., said point is 634.7-ft N. 76° 45' W. of Sta. 198+20, which station is tied to the N.E. corner of Sec. 1 as shown on the map; thence, along the said alley line, south for 25.0-ft to the N.E. corner of lot 11; thence, along the north line of lot 11, west for 74.2-ft; thence S. 76° 45' W. for 74.2-ft to a point on the west line of the alley of block 6; thence, along the said alley line, north for 17.0-ft to the N.E. corner of lot 11, the point of beginning.

Said right-of-way contains 613.7 sq. ft. or 0.014 acres, all of which is to be acquired.



SCALE 1 IN. = 100 FT

NW 1/4 of Sec. 1
T. 15 R. 76 W.

H. F. VOLGAST
S. S. GARRETT


Convey all of the land situated within the Right-of-Way, said Right-of-Way extends 50.0-ft on each side of the center line of the Highway, except as otherwise noted, said Highway is located in the N. 1/2 of Sec. 1, T. 15, R. 76 W. of the 6th Principal Meridian; more particularly described as follows:

Beginning at Sta. 198+20, a point on the north and south 1/2 line of Sec. 1, whence the north 1/2 corner bears North, 1335.0-ft.; thence, along the said 1/2 line North for 15.0-ft to a point on the north 1/16 line of Sec. 1; thence, along the 1/16 line, east for 14.6-ft; thence N. 76° 45' W. for 427.0-ft; thence S. 13° 15' N. for 11.0-ft; thence S. 76° 45' W. for 53.4-ft to a point on the west property line of Block 4 of the town of Tabernash; thence, along said property line, south for 143.9-ft; thence N. 13° 15' E. for 50.0-ft; thence S. 76° 45' E. for 291.3-ft to a point on the north and south 1/2 line of Sec. 1; thence, along the said 1/2 line, north for 41.4-ft to the point of beginning.

Said Right-of-Way contains 1.761 acres, of which 0.106 acres is contained within the right-of-way of the old road, and of which 0.655 A. is to be acquired.

TABERNASH

Main St.



SCALE: 1"=100' FT


NW 1/4 Sec 1
T1S. R76W


EDNA J. LOCKE
D. D. LOCKE

Convey all of the land situated within the Right-of-Way, said Right-of-Way extends 40.0-ft. on each side of the center line of the Highway, said Highway is located in Lot 1, Block 7, Town of Tabernash, in the N.W. 1/4 of Sec. 1, T. 1S., R. 76W., of the 6th Principal Meridian; more particularly described as follows:

Beginning at Sta. 209+75.4, a point on the west property line of 3rd St., 47.9-ft. south of the N.E. corner of Block 7, and 319.5-ft. S. 76° 45' E. of P.I. 212+94.9, which P.I. is tied to the N.W. corner of Sec. 1 as shown on the Map. Thence, along said west property line, north for 41.1-ft.; thence N. 76° 45' E. for 12.2-ft. to a point on the south property line of Main St.; thence, along said south property line, west for 113.1-ft.; thence south for 50.0-ft.; thence along the south line of Lot 1, east for 125.0-ft. to a point on the west property line of 3rd St.; thence, along the said west property line, north for 5.1-ft. to the point of beginning.

Said Right-of-Way contains 6233.3 square feet, or 0.143 acres, all of which is to be acquired.






H. B. WALKER

Conveys all of the land situated within the Right-of-Way, said Right-of-Way extends 40.0-ft. on each side of the center line of the Highway, said Highway is located in the Lot 16, Block 6, Town of Tabernash, in the N.W. 1/4 of Sec. 1, T.15S., R.76W., of the 6th Principal Meridian; more particularly described as follows:

Beginning at Sta. 209+13.8, a point on the east property line of 3rd St., 52.0-ft. south of the N.W. corner of Block 6, and 125.1-ft. N. 76° 45' W. of Sta. 198+20, which station is tied to the N.E. corner of Sec. 1 as shown on the Map. Thence, along the said east property line, North for 3.0-ft. to the S.W. corner of Lot 16; thence east for 125.0-ft.; thence North for 3.7-ft.; thence N. 76° 45' W. for 128.4-ft. to the east property line of 3rd St.; thence, along said east property line, south for 34.1-ft. to the S.W. corner of Lot 16, the point of beginning.

Said Right-of-Way contains 2300.0 square feet, or 0.053 acres, all of which is to be acquired.



SCALE: 1"=100' FT


NW 1/4 Sec 1
T. 15. N. 76. W.

ROY FOX
HARRY FOX
J. B. HODGE

Convey all of the land situated within the right-of-way, said right-of-way extends 40.0-ft. on each side of the center line of the Highway, said Highway is located in Lot 2, Block 7, Town of Tabernash, in the NW 1/4 of Sec. 1, T. 15. N. 76. W. of the 6th Principal Meridian; more particularly described as follows:

Beginning at Sta. 209+75.4, a point on the west property line of 3rd. St., 43.2-ft. south of the N.E. corner of Block 7, and 119.5-ft. S. 76° 45' E. of P.I. 212+94.9, which P.I. is tied to the N.W. corner of Sec. 1, as shown on the Map. thence, along said west property line south for 6.1-ft. to the N.E. corner of Lot 2; thence, along the north lot line, west, for 12.0-ft.; thence south for 7.4-ft.; thence S. 76° 45' E. for 125.4-ft. to the west property line of 3rd. St.; thence, along the said west property line, north, for 35.0-ft. to the N.E. corner of Lot 2, the point of beginning.

Said right-of-way contains 2537.5-square feet, or 0.583 acres, all of which is to be acquired.



SCALE 1IN = 100-FT


NW 1/4 Sec 1
T15S. R76W

JOHN A. SWIDER

Conveys all of the land situated within the right-of-way, said right-of-way extends 40.0-ft. on each side of the center line of the highway, said Highway is located in Lot 16, Block 7, Town of Tabernash, in the NW 1/4 of Sec. 1, T15S., R.76W. of the 6th Principal Meridian; more particularly described as follows:

Beginning at Sta. 211+16.1, a point on the west line of the alley of block 7, - 11.7-ft. south of the south line of Main St., and 178.3-ft. S.76°45'E. of P.I. 212+94.9, which P.I. is tied to the N. 1/2 corner of Sec. 1 as shown on the Map. thence north for 11.7-ft. to the south property line of Main St.; thence, along said property line, east, for 125.0-ft. to the east property line of 4th St.; also the N.W. corner of block 7; thence, along said east property line, south for 22.8-ft.; thence on a curve to the left with a radius of 1472.5-ft. for 3.4-ft.; thence S.76°45'E. for 39.1-ft. to a point on the west line of the alley of block 7; thence, along said west alley line, north, for 41.1-ft. to the point of beginning.

Said right-of-way contains 2350.0 square feet or 0.065 acres, all of which is to be acquired.



Scale 1"=100'-0"

IDA E. CRISSELL

N.E. 1/4 Sec 19
T.15. R.75 W.

FRASER


Conveys all of the land situated within the right-of-way, said right-of-way extends 40.0-ft. on each side of the center line of the highway, except as otherwise noted, said highway is located in Lots 1 to 11, Block 10; Lots 42 to 43, Block 10; and Lot 7, Block 7; Town of Fraser, in the N.E. 1/4 of Sec. 19, T.15. R.75 W. of the 6th Principal Meridian; more particularly described as follows:


Beginning at Sta. 2+79.4, a point on the north property line of Easton Ave. 136.3-ft. east of the S.W. corner of Block 10, and 429.4-ft. N.23°52'W. of Sta. 5+50, which station is tied to the N.E. corner of Sec.19 as shown on the Map. thence, along said property line, N.33°53'W. for 207.0-ft.; thence N.15°22'W. for 140.7-ft.; thence S.33°53'E. for 246.5-ft.; thence S.23°52'E. for 102.2-ft.; thence S.10°03'W. for 10.0-ft.; thence S.23°52'E. for 43.2-ft. to the north line of Easton Ave.; thence, along said north property line, N.33°53'W. for 45.2-ft. to the point of beginning.

Beginning at Sta. 11+54.7, a point on the north line of the alley of block 10, 135.9-ft. east of the east line of block 10, and 504.7-ft. N.23°52'W. of Sta. 5+50, which station is tied to the N.E. corner of Sec.19 as shown on the Map. thence, along the said alley line, N.33°53'W. for 164.5-ft.; thence N.15°22'W. for 140.7-ft. to the south line of Park Ave.; thence, along said south property line, S.33°53'E. for 134.2-ft.; thence, on a curve to the left with a radius of 2815.3-ft. for 22.5-ft.; thence S.23°52'E. for 120.9-ft. to the north line of the alley of Block 10; thence, along the said north alley line, N.33°53'W. for 57.3-ft. to the point of beginning.

Beginning at Sta. 9+11.6, a point on the south property line of Easton Ave. 242.7-ft. east of the N.W. corner of block 7, and 361.6-ft. N.23°52'W. of Sta. 5+50, which station is tied to the N.E. corner of Sec.19 as shown on the Map. thence, along the said south property line, N.33°53'W. for 37.2-ft. to the N.E. corner of Lot 7; thence S.10°02'W. for 13.3-ft.; thence N.23°52'W. for 17.1-ft. to the south property line of Easton Ave.; thence, along the said south property line, S.33°53'E. for 8.0-ft. to the N.E. corner of Lot 7, the point of beginning.

Said right-of-way contains 53,061.8 square feet, or 1.218 acres, all of which is to be acquired.





NE 1/4 Sec. 19
T. 1 S. R. 75 W.

FRASER


DAVID MORANSON

Conveys all of the land situated within the Right-of-Way, said Right-of-Way extends 40.0ft on each side of the center line of the Highway, said Highway is located in Lots 1 to 13, and 24 to 37, all in block 7, town of Fraser, T. 1 S. R. 75 W. of the 6th Principal Meridian; more particularly described as follows:

Beginning at Sta. 2411.6, a point on the south property line of Easton Ave., 242.7ft east of the N.W. corner of block 7, and 561.6ft, N.23°52'W. of Sta. 5450, which station is tied to the N.E. corner of Sec. 19 as shown on the Map. Thence, along the said south property line, N.88°53'W. for 37.2ft; thence S.31°02'W. for 15.2ft; thence S.33°12'W. for 135.6ft to the north line of the alley of block 7; thence, along said north alley line, S.33°53'E. for 90.4ft; thence N.23°52'W. for 152.7ft to the south property line of Easton Ave.; thence, along said south property line, N.30°53'W. for 45.2ft to the point of beginning.

Beginning at Sta. 736.3, a point on the south line of the alley of block 7, 233.6ft east of the west line of block 7, and 176.3ft, N.23°52'W. of Sta. 5450, which station is tied to the N.E. corner of Sec. 19 as shown on the Map. Thence, along the said south alley line, N.33°53'E. for 45.2ft; thence S.23°52'E. for 110.7ft; thence N.01°02'E. for 77.9ft to the south alley line of block 7; thence, along the said south alley line, N.88°53'W. for 6.5ft to the point of beginning.

Said Right-of-Way contains 14,746.7 square feet, or 0.339 acres, all of which is to be acquired.



N.E. 1/4 Sec. 19
T. 1 S. R. 75 W.


FRASER

MATTIE JOHNSON

Conveys all of the land situated within the Right-of-Way, said Right-of-Way extends 40.0ft on each side of the center line of the Highway, said Highway is located in Lot 34, Block 7, Town of Fraser, in the ... of Sec. 19, T. 1 S., R. 75 W. of the 6th Principal Meridian; more particularly described as follows:

Beginning at Sta. 7+36.3, a point on the south line of the alley of Block 7, 233.6ft east of the west line of Block 7, and 1'6.3ft N. 23° 52' W. of Sta. 5+50, which Sta. is tied to the N.E. corner of Sec. 19 as shown on the Map. Thence, along the said south alley line, S. 33° 58' E. for 2.5ft to the N.E. corner of Lot 34; thence, along the west lot line, S. 01° 02' W. for 7.9ft; thence S. 29° 22' E. for 42.0ft to the north property line of Fraser Ave.; thence, along said property line, S. 33° 51' E. for 5.4ft; thence N. 01° 02' E. for 135.0ft to the south line of the alley; thence, along the said south alley line, N. 33° 58' E. for 2.5ft to the N.W. cor of Lot 34, the point of beginning.

Said Right-of-Way contains 331.2 square feet, or 0.009 acres, all of which is to be acquired.



NE 1/4 Sec. 19
T. 1 S. R. 75 W.


FRAZER

M. R. EVANS

Conveys all of the land situated within the Right-of-way, said Right-of-way extends 40.0-ft. on each side of the center line of the highway, said Right-of-way is located in Lot 33, Block 7, Town of Fraser, in the N.E. 1/4 of Sec. 19, T. 1 S. R. 75 W. of the 6th Principal Meridian; more particularly described as follows:

Beginning at Sta. 5+83.6, a point on the north property line of Fraser Ave 319.4-ft. east of the S.W. corner of Block 7, and 33.6-ft. N. 28° 52' W. of Sta. 5+50, which station is tied to the N.E. corner of Sec. 19 as shown on the Map. Thence, along the said north property line, S. 33° 53' W. for 14.3-ft. to the S.E. corner of 1st 32; thence N. 01° 02' E. for 113.6-ft.; thence N. 28° 52' W. for 24.2-ft. to the south line of the alley of Block 7; thence, along said alley line, S. 38° 53' W. for 13.7-ft.; thence S. 01° 02' W. for 135.0-ft. to a point on the north property line of Fraser Ave.; thence, along said north property line, S. 38° 53' W. for 13.7-ft. to the S.W. corner of Lot 33, the point of beginning.

Said Right-of-way contains 1254.1 square feet, or 0.074 acres, all of which is to be acquired.



IVOR FLORQUIST


Conveys all of the land situated within the Right-of-Way, said Right-of-Way extends 40.0ft on each side of the center line of the Highway, said Highway is located in 31, and 32, Block 7, Town of Fraser, in the N.E. 1/4 of Sec. 19, T.13S., R.75W., of the 6th Principal Meridian; more particularly described as follows:

Beginning at Sta. 5+33.6, a point on the north property line of Frazer Ave. 31.4ft east of the S.W. corner of Block 7, and 33.6ft N.24°50'W. of Sta. 5+50, which Station is tied to the N.E. corner of Sec. 19 as shown on the Map. Thence, along said north property line, N.88°53'E. for 14.3ft; thence N.01°02'E. for 113.4ft; thence S.23°52'E. for 107.1ft; thence S.01°02'E. for 13.9ft to the north property line of Frazer Ave.; thence, along the said north property line, S.39°51'W. for 75.2ft to the point of Beginning.

Said Right-of-Way contains 3317.5 square feet, or 0.076 acres, all of which is to be acquired.

N.E. 1/4 Sec 19
T.13S. R.75W.

FRASER



ROBERT FLORQUIST
B. B. BENSON

Convey all of the land situated within the right-of-way, said Right-of-Way extends 40.0-ft. on each side of the center line of the Highway, said Highway is located in Lot 30, Block 7, Town of Frazer, in the N.E. 1/4 of Sec. 19, T. 1 S., R. 75 W. of the 6th Principal Meridian; more particularly described as follows:

Beginning at Sta. 5+83.6, a point on the north property line of Frazer Ave. 219.4-ft. east of the S.W. corner of Block 7, and 53.6-ft. S. 28° 52' E. of Sta. 5+50, which station is tied to the N.E. corner of Sec. 19 as shown on the Map. Thence, along said north property line, S. 88° 53' E. for 35.2-ft. to the S.W. corner of Lot 30; thence N. 01° 02' E. for 15.0-ft.; thence S. 28° 52' E. for 21.4-ft. to the north property line of Frazer Ave.; thence, along said north property line, S. 88° 53' E. for 10.0-ft. to the S.W. corner of Lot 30, the point of beginning.

Said right-of-way contains 94.5-square feet, all of which is to be acquired


12576 1125 2516
NOV 1936
FED. H. V.
S. P. H.

IDA E. CHISELL

Conveys all of the land situated within the right-of-way, said right-of-way extends 40.2-ft. on each side of the center line of the highway, said highway is located in Lot 12, Block 6, Town of Frazer, in the N.E. 1/4 of Sec. 19, T. 13S., R. 75W., of the 6th Principal Meridian; more particularly described as follows:

Beginning at Sta. 5+15.3, a point on the south property line of Frazer Ave. 335.1-ft. east of the N.W. corner of Block 6, and 34.2-ft. S. 23° 52' E. of Sta. 5+50, which station is tied to the N.E. corner of Sec. 19 as shown on the Map. Thence, along the said north property line, N. 8° 53' E. for 20.3-ft. to the N.E. corner of Lot 12; thence S. 91° 32' E. for 49.6-ft.; thence N. 22° 52' W. for 52.3-ft. to the south property line of Frazer Ave.; thence, along the said south property line, S. 13° 53' E. for 34.4-ft. to the N.E. corner of Lot 12, the point of beginning.

Said Right-of-Way contains 565.6 square feet, all of which is to be acquired.




N.E. 1/4 Sec. 19
T. 13S. R. 75W.

FRAZER

Sta 0+00 of FAP 151-A - Sta 855+00
of B PR Project East of Frazer

SCALE: 1 in = 100 FT.



CARL KRANSON

N.E. 1/4 Sec. 19
T. 15. N. 75. W.

FRAZER

Conveys all of the land situated within the right-of-way, said Right-of-way extends 40.0-ft. on each side of the center line of the Highway, said Highway is located in Lots 13 and 14, Block 6, Town of Frazer, in the N.E. 1/4 of Sec. 19, T. 15. N. 75. W. of the 4th Principal Meridian; more particularly described as follows:

Beginning at Sta. 5+15.8, a point on the south property line of Frazer Ave. 335.1-ft. east of the N.E. corner of Block 6, and 34.2-ft. S. 23° 52' E. of Sta. 5+50, which station is tied to the N.E. corner of Sec. 19 as shown on the Map. Thence, along said south property line, N. 87° 58' W. for 10.3-ft.; thence S. 21° 02' E. for 46.2-ft.; thence S. 28° 52' E. for 100.4-ft.; thence S. 88° 58' E. for 1.1-ft.; thence S. 01° 02' E. for 135.1-ft. to the south property line of Frazer Ave.; thence, along said south property line, N. 88° 58' E. for 29.2-ft. to the point of beginning.

Said Right-of-way contains 4667.6 square feet or 0.107 acres, all of which is to be acquired.




MATT WALKER
E. R. MATTS

Convey all of the land situated within the Right-of-Way, said Right-of-Way extends 40.0-ft. on each side of the center line of the highway, said highway is located in 15 and 16, Block 6, Town of Frazer, in the N.E. 1/4 of Sec. 19, T.15S., R.75W. of the 6th principal meridian; more particularly described as follows:

Beginning at Sta. 3+53.1, a point on the north line of the alley of Block 6, 371.1-ft. east of the west line of Block 6, and 136.9-ft. S. 28° 52' E. of Sta. 5+50, which station is tied to the N.E. corner of Sec. 19 as shown on the Map. Thence, along said north alley line, N. 88° 58' W. for 42.1-ft.; thence, S. 81° 02' E. for 155.3-ft. to the south property line of Frazer Ave.; thence, along said south property line, S. 88° 58' W. for 16.0-ft.; thence S. 28° 52' E. for 42.3-ft.; thence S. 1° 02' N. for 70.6-ft. to the north line of the alley; thence, along said north alley line, N. 88° 58' W. for 7.9-ft. to the point of beginning.

Said Right-of-Way contains 1655.2-square feet or 0.129 acres, all of which is to be acquired.



N.E. 1/4 Sec. 19
T.15S. R.75W.

FRAZER


Sta 0+00 of FAP 151-A - Sta 855+00
of B.P.R. Project East of Frazer

E. B. WATTS

Conveys all of the land situated within the Right-of-Way, said Right-of-Way extends 40.0-ft. on each side of the center line of the Highway, said Highway is located in Lots 17 and 18, Block 6, Town of Fraser, in the N.E. 1/4 of Sec. 19, T.1S., R.75W. of the 6th Principal Meridian; more particularly described as follows:

Beginning at the S.W. corner of Lot 17, which lot corner is 7.9-ft. - S. 88° 58' E. of Sta. 5+63.1, a point on the north line of the alley of Block 6, 371.1-ft. east of the west line of Block 6, and 186.9-ft. S. 28° 52' E. of Sta. 5+50 which station is tied to the N.E. corner of Sec. 19 as shown on the Map. Thence, from the said S.W. corner of Lot 17, N. 01° 02' E. for 70.6-ft.; thence S. 28° 52' E. for 79.9-ft. to the north line of the alley; thence, along the said north alley line, N. 88° 58' W. for 37.3-ft. to the S.W. corner of Lot 17, the point of beginning.

Said Right-of-Way contains 1306.7-square feet, or 0.030 acres, all of which is to be acquired.




Scale 1 in = 100 ft.

E. B. WATTS

Conveys all of the land situated within the Right-of-Way, said Right-of-Way extends 40.0-ft. on each side of the center line of the Highway, said Highway is located in Lots 17 and 18, Block 6, Town of Frazer, in the N.E. 1/4 of Sec. 19, T.18N., R.75W. of the 6th Principal Meridian; more particularly described as follows:

Beginning at the S.W. corner of Lot 17, which lot corner is 7.9-ft. - S. 88° 58' E. of Sta. 3+63.1, a point on the north line of the alley of Block 6, 371.1-ft. east of the west line of Block 6, and 186.9-ft. S. 28° 52' E. of Sta. 5+50 which station is tied to the N.E. corner of Sec. 19 as shown on the Map. Thence, from the said S.W. corner of Lot 17, N. 0° 02' E. for 70.6-ft.; thence S. 23° 52' E. for 79.9-ft. to the north line of the alley; thence, along the said north alley line, N. 88° 58' W. for 37.3-ft. to the S.W. corner of Lot 17, the point of beginning.

Said Right-of-Way contains 1306.7-square feet, or 0.030 acres, all of which is to be acquired.




O. G. TRYON

Conveys all of the land situated within the Right-of-Way, said Right-of-Way extends 40.0-ft. on each side of the center line of the Highway, said Highway is located in Lots 25 and 26, Block 6, Town of Fraser, in the N.E. 1/4 of Sec. 19 T.1S., R.75W. of the 6th Principal Meridian; more particularly described as follows:

Beginning at the N.E. corner of Lot 25, which Lot corner is 2.6-ft. - N. 89° 59' 18" of Sta. 3+40.5, a point on the south line of the alley of Block 6, 374.3-ft. east of the west line of Block 6, and 209.5-ft. - S. 28° 52' E. of Sta. 5+50 which station is tied to the N.E. corner of Sec. 19 as shown on the Map. Thence, from the said N.E. corner of Lot 25, S. 01° 02' W. for 80.7-ft.; thence N. 28° 52' W. for 91.2-ft. to the south line of the alley; thence, along the said south alley line, S. 88° 58' E. for 42.6-ft. to the N.E. corner of Lot 25, the point of beginning.

Said Right-of-Way contains 3437.8-square feet, or 0.079 acres, all of which is to be acquired.




ALLIANCE
all of the land situated within the Right-of-Way, said Right-of-Way extends 40.0-ft. on each side of the center line of the highway, said Highway is located in Lot 24, Block 6, Town of Frazer, in the NE 1/4 of Sec. 19, T. 15 N., R. 75 W., or the 6th Principal Meridian; more particularly described as follows:

Beginning at Sta. 5+00.5, a point on the south line of the alley of Block 6, 354.8-ft. east of the west line of block 6, and 205.5-ft. - 3.23° 52' E. of Sta. 5+50, which station is tied to the N.E. corner of Sec. 19 as shown on the map. thence, along said alley line, N. 38° 58' E. for 2.6-ft.; thence S. 01° 02' W. for 20.7-ft.; thence S. 28° 52' E. for 45.4-ft.; thence S. 01° 02' W. for 127.8-ft. to the south line of the alley; thence, along said alley line, N. 38° 58' W. for 22.4-ft. to the point of beginning.

Said Right-of-Way contains 2706.3 square feet, or 0.060 acres, all of which is to be acquired.

Scale 1 in. = 100 ft.





L. O. GRAVES

Conveys all of the land situated within the Right-of-Way, said Right-of-Way extends 40.0-ft. on each side of the center line of the Highway, said Highway is located in Lot 23, Block 6, Town of Frazer, in the N.E. 1/4 of Sec. 19, T. 18., R. 75W. of the 6th Principal Meridian; more particularly described as follows:

Beginning at the S.E. corner of Lot 23, which corner is 24.0-ft. N. 88° 58' W. of Sta. 1+87.8, a point on the north property line of St. Louis Ave. 410.2-ft. - east of the S.W. corner of Block 6, and 562.2-ft. S. 28° 52' E. of Sta. 5+50, which station is tied to the N.E. corner of Sec. 19 as shown on the Map. Thence, from the said S.E. corner of Lot 23, N. 01° 02' E. for 130.8-ft.; thence N. 28° 52' E. for 4.7-ft.; thence N. 88° 58' W. for 22.8-ft.; thence S. 01° 02' W. for 127.8-ft.; thence S. 28° 52' E. for 8.1-ft. to the north property line of St. Louis Ave.; thence, along the said north property line, S. 88° 58' E. for 21.2-ft. to the S.E. corner of Lot 23 the point of beginning.

Said Right-of-Way contains 3355.0-square feet, or 0.077 acres, all of which is to be acquired.





Sta 0+00 of FAP 151-A: Sta 855+00
of BPR Project East of Frazer

HAZEL ROBBINS
BERTHA GILBA

Convey all of the land situated within the Right-of-Way, said Right-of-way extends 40.0-ft. on each side of the center line of the Highway, said Highway is located in Lot 22, Block 6, town of Frazer, in the N.E. 1/4 of Sec. 19, T. 1 S., R. 75 W. of the 6th Principal Meridian; more particularly described as follows:

Beginning at Sta. 1+37.8, a point on the north property line of St. Louis Ave., 410.2-ft. east of the S.W. corner of Block 6, and 362.2-ft. S. 28° 52' E. of Sta. 5+50, which station is tied to the N.E. corner of Sec. 19, as shown on the map. Thence, along the said north property line, N. 38° 58' E. for 24.0-ft.; thence N. 01° 02' E. for 130.8-ft.; thence S. 28° 52' E. for 53.5-ft.; thence S. 01° 02' E. for 23.5-ft. to the north property line of St. Louis Ave.; thence, along the said north property line, N. 38° 58' E. for 1.0-ft. to the point of beginning.

Said right-of-way contains 2688.0 square feet, or 0.061 acres, all of which is to be acquired.


BERTHA GILBA

Conveys all of the land situated within the Right-of-Way, said Right-of-Way extends 40.0-ft. on each side of the center line of the Highway, said Highway is located in lot 21, Block 6, and Lots 26 and 27, of the Lake Site Sub-division, Town of Frazer, in the N.E. 1/4 of Sec. 19, T. 18, R. 75W. of the 6th Principal Meridian; more particularly described as follows:

Beginning at the S.W. corner of Lot 21, which corner is 1.0-ft. S. 88° 58' E. of Sta. 1+87.8, a point on the north property line of St. Louis Ave. - 410.2-ft. east of the S.W. corner of Block 6, and 362.2-ft. S. 28° 52' E. of Sta. 5+50, which station is tied to the N.E. corner of Sec. 19 as shown on the Map. Thence, from the said S.W. corner of Lot 21, N. 01° 02' E. for 83.5-ft.; thence S. 28° 52' E. for 53.5-ft.; thence S. 01° 02' W. for 36.2-ft. to the north property line of St. Louis Ave.; thence, along the said north property line, S. 88° 58' W. for 25.0-ft. to the S.W. corner of Lot 21, the point of beginning.

Beginning at a point on the west line of Lake Site Sub-division, which point is 29.0-ft. S. 88° 58' E. of Sta. 1+08.6, a point on the south property line extended of St. Louis Ave. - 11.0-ft. east of the N.E. corner of Block 5, and 441.4-ft. S. 28° 52' E. of Sta. 5+50, which station is tied to the N.E. corner of Sec. 19 as shown on the Map. Thence, from said point on the west line of Lake Site Sub-division, S. 01° 02' W. for 20.0-ft.; thence S. 88° 58' E. for 26.4-ft.; thence N. 01° 02' E. for 56.5-ft. to the west line of the Sub-division; thence, along said west line, S. 01° 02' W. for 30.0-ft. to the point of beginning.

Said Right-of-Way contains 2157.5 square feet, or 0.050 acres, all of which is to be acquired.




JOHN BARRER
BERTHA GILBA

Convey all of the land situated within the right-of-way, said right-of-way extends 40.0-ft. on each side of the center line of the Highway, said Highway is located in Lots 28 and 29, Lake Site Subdivision, Town of Frazer, in the N.E. 1/4 of Sec. 19, T.18., R.75W. of the 6th Principal Meridian; more particularly described as follows:

Beginning at Sta. C+46.4, a point on the west line of Lake Site Subdivision, 127.5-ft. north of the S.W. corner of the Subdivision, and 503.6-ft. - S.23°52'E. of Sta. 5+50, which station is tied to the N.E. corner of Sec. 19 as shown on the Map. Thence, along the said west line, S.01°02'W. for 15.0-ft.; thence S.33°58'E. for 53.1-ft.; thence N.28°52'W. for 56.5-ft.; thence N.98°58'W. for 26.4-ft. to the west line of the Subdivision; thence, along said west line, S.01°02'W. for 35.0-ft. to the point of beginning.

Said right-of-way contains 1987.5-square feet, or 0.046 acres, all of which is to be acquired.




SCALE: 1 IN. = 100 FT.

W. H. EDWARDS


Conveys all of the land situated within the Right-of-Way, said Right-of-Way extends 40.0-ft. on each side of the center line of the Highway, said Highway is located in Lots 30 and 31, Lake Site Sub-division, Town of Frazer, in the N.E. 1/4 of Sec. 19, T.18., R.75W. of the 6th Principal Meridian; more particularly as follows:

Beginning at the N.W. corner of Lot 30, which corner is 15.0-ft. S. 01° 02' W. of Sta. 0+46.4, a point on the west line of Lake Site Sub-division, - 127.5-ft. north of the S.W. corner of the Sub-division, and 503.6-ft. S. 28° 52' E. of Sta. 5+50, which station is tied to the N.E. corner of Sec. 19 as shown on the Map. Thence, from the said N.W. corner of Lot 30, S. 88° 58' E. for 53.1-ft.; thence S. 28° 52' E. for 8.1-ft.; thence S. 61° 08' W. for 64.5-ft. to the west line of the Sub-division; thence, along said west line, N. 01° 02' E. for 37.5-ft. to the N.W. corner of Lot 30, the point of beginning.

Said Right-of-Way contains 1261.2-square feet or 0.029-acres, all of which is to be acquired.



Scale: 1 in. = 100 ft.



A. E. ZAHN

Conveys all of the land situated within the Right-of-Way, said Right-of-Way extends 40.0-ft. on each side of the center line of the Highway, said Highway is located in Lot 16, Block 5, Town of Fraser, in the N.E. 1/4 of Sec. 19, T. 13 S., R. 75 W. of the 6th Principal Meridian; more particularly described as follows:

Beginning at the N.E. corner of Lot 16, also the N.E. corner of Block 5, which corner is 11.0-ft. N. 88° 58' W. of Sta. 1+08.6, a point on the south property line extension of St. Louis Ave.; thence S. 17° 42' E. for 17.4-ft. to the N.E. corner of Lot 16, also the N.E. corner of Block 5, as shown on the Map. Thence, from the said N.E. corner of Lot 16, S. 01° 02' E. for 64.8-ft.; thence N. 28° 52' W. for 53.5-ft.; thence N. 01° 02' E. for 17.4-ft. to the south property line of St. Louis Ave.; thence, along the said south property line, S. 88° 58' E. for 25.0-ft. to the N.E. corner of Lot 16, the point of beginning.


Said Right-of-Way contains 1027.5 square feet, or 0.024 acres, all of which is to be acquired.

E. B. WATTS

Conveys all of the land situated within the Right-of-Way, said Right-of-Way extends 40.0-ft. on each side of the center line of the Highway, said Highway is located in Lot 15, Block 5, Town of Fraser, in the N.E. 1/4 of Sec. 19, T.15., R.75W. of the 6th Principal Meridian; more particularly described as follows:

Beginning at the N.E. corner of Lot 15, which corner is 36.0-ft. - N. 38° 58' W. of Sta. 1+08.6, a point on the south property line extending of St. Louis Ave., which point is 441.4-ft. - S. 23° 52' E. of Sta. 5+90, which station is tied to the N.E. corner of Sec. 13 as shown on the Map. Therefrom, from the said N.E. corner of Lot 15, S. 01° 02' W. for 17.4-ft.; thence, N. 28° 52' E. for 19.7-ft. to the south property line of St. Louis Ave.; thence, along the said south property line, S. 88° 58' E. for 9.2-ft. to the N.E. corner of Lot 15, the point of Beginning

Said Right-of-Way contains 300.4 square feet, or 0.018 acres, all of which is to be acquired.






D. L. Co., S. B. Co.,
C. W. P. Co., H. L. C. Co.

Convey all of the land situated within the Right-of-Way, said Right-of-Way extends 40.0-ft. on each side of the center line of the Highway, except as otherwise noted; said Highway is located in the N.W. 1/4 of the N.E. 1/4 of Sec. 19, T.15S., R.75W. of the 6th Principal Meridian; more particularly described as follows:


Beginning at Sta. 22+70, a point on the north section line of Sec. 19, whence the N.E. corner of Sec. 19 bears: East, 1697.0-ft.; thence, along the said section line, east for 52.9-ft.; thence, south-easterly, on a curve to the left with a radius of 5680.0-ft. for 65.8-ft.; thence S.19°04'E. for 442.5-ft.; thence on a curve to the left with a radius of 2815.0-ft. for 392.9-ft. to a point on the north property line of Park Ave. in the Town of Frazer; thence, along said north property line, N.88°58'W. for 168.0-ft.; thence N.15°13'W. for 483.4-ft.; thence S.19°04'W. for 106.9-ft. to a point on the north section line of Sec. 19; thence, along the said section line, East, for 52.9-ft. to the point of beginning.

Said Right-of-Way contains 2.249 acres, of which 0.218 acres is contained within the Right-of-Way of the old road, and of which 2.031 acres is to be acquired.





Scale 1" = 200'



Conveys all of the land situated within the Right of Way; said Right of Way extends 100.0 feet on the left and 50.0 feet on the right side of the center line of the Highway, except where otherwise noted; said Highway is located in the S.E.¼ of the S.W.¼ of Section 32, T.2 N., R.76 W. of the 6th Principal Meridian, more particularly described as follows:


Said Right of Way contains 3.074 acres of cultivated land, all of which is to be acquired.

Note: Shaded portion of map is that which is to be acquired.

T.1N.-R.75W.-6th PM.
Section 6



Colorado State Highway Dept.
Federal Aid Project No.151-C
Right of Way Map No.2



T.2N.-R.76W.-6th PM.
Section 32

J. N. OSTRANDER

Conveys all of the land situated within the Right of Way; said Right of Way extends 100.0 feet on each side of the center line of the Highway, except where otherwise noted; said Highway is located in the S. 1/4 of the N.E. 1/4, and in the N.E. 1/4 of the S.E. 1/4, all in Section 6, T.1 N., R.76 W. of the 6th Principal Meridian, more particularly described as follows:

Beginning at center line Station 47+02.0, a point on the South, East & West 1/16 line of Section 6, whence the S.E. corner of Section 6 bears S.34°16'E. for 1558.0 feet; thence along said 1/16 line, N.89°45'W. for 82.7 feet; thence S.14°30'W. for 440.9 feet; thence S.75°30'W. for 20.0 feet; thence S.14°30'W. for 855.2 feet, to the East & West 1/16 line of Section 6; thence N.14°30'W. for 144.8 feet; thence S.75°30'E. for 80.0 feet; thence S.14°30'W. for 1150.0 feet to the North, East & West 1/16 line of Section 6; thence along said 1/16 line, S.89°57'E. for 105.4 feet; thence S.14°30'E. for 1104.0 feet; thence S.75°30'E. for 80.0 feet; thence S.14°30'E. for 197.2 feet, to the East & West 1/16 line of Section 6; thence S.14°30'E. for 808.8 feet; thence S.75°30'W. for 20.0 feet; thence S.14°30'W. for 483.1 feet to the South, East & West 1/16 line of Section 6; thence along said 1/16 line, N.69°45'W. for 82.7 feet to the point of beginning.

Said Right of Way contains 6.956 acres of cultivated and 1.897 acres of uncultivated land, a total of 8.853 acres, all of which is to be acquired.

Note: Shaded portion of map is that which is to be acquired.

A. F. POLHAMUS
Conveys all of the land situated within the Right of Way; said Right of Way extends 50.0 feet on each side of the center line of the Highway, except where otherwise noted; said Highway is located in the N.E. 1/4 of the N.E. 1/4, and in the N.E. 1/4 of the S.E. 1/4, all in Section 6, T.1 N., R.76 W. of the 6th Principal Meridian, more particularly described as follows:

Beginning at center line station 8+04, a point on the Township Line between T.1 N. and T.2 N., whence the S.E. corner of Section 32, T.2 N., R.76 W. of the 6th Principal Meridian, bears S.69°57'E. for 427.2 feet; thence along said Township Line, S.89°57'E. for 166.3 feet, to a point on the Right of Way line on the right side of the center line; thence on a curve to the right, with a radius of 616.3 feet, for 188.8 feet, to the North Right of Way line of the Denver & Salt Lake R.R.; thence along said R.R.R.O.W. line, S.82°06'E. for 266.7 feet, to a point on the left R.O.W. line of the Highway; thence on a curve to the left, with a radius of 616.3 feet, for 190.2 feet, to a point on the North Township Line of T.1 N.; thence along said Township Line S.89°57'E. for 138.1 feet, to the point of beginning.

Said Right of Way contains 0.618 acres of uncultivated and 0.246 acres of cultivated land, a total of 0.864 acres, all of which is to be acquired.

Note: Shaded portion of map is that which is to be acquired.

A. F. POLHAMUS
Conveys all of the land situated within the Right of Way; said Right of Way extends 50.0 feet on each side of the center line of the Highway, except where otherwise noted; said Highway is located in the N.E. 1/4 of the N.E. 1/4 of Section 6, T.1 N., R.76 W., of the 6th Principal Meridian, more particularly described as follows:

Beginning at center line Station 12+62.0, a point on the South Right of Way line of the Denver & Salt Lake R.R., whence the S.E. corner of Section 32, T.2 N., R.76 W. of the 6th Principal Meridian, bears N.31°09'E. for 417.1 feet; thence along said R.R.R.O.W. line, S.82°06'E. for 84.1 feet; thence S.14°30'E. for 480.4 feet; thence S.40°21'E. for 130.1 feet; thence S.75°30'E. for 370.8 feet; thence S.22°11'W. for 268.0 feet; thence S.46°42'W. for 100.0 feet; thence S.40°21'W. for 144.2 feet; thence S.75°30'W. for 105.1 feet; thence S.14°30'E. for 746.0 feet, to the North 1/16 line of Section 6; thence along said 1/16 line N.29°57'W. for 103.4 feet; thence N.14°30'W. for 220.0 feet; thence S.75°30'W. for 408.7 feet; thence N.28°47'E. for 383.7 feet; thence N.65°41'E. for 148.9 feet; thence S.14°30'W. for 387.0 feet; thence on a curve to the left, with a radius of 466.3 feet, for 11.9 feet, to a point on the South Right of Way line of the Denver & Salt Lake R.R.; thence S.82°06'E. for 54.2 feet, to the point of beginning.

Said Right of Way contains 0.489 acres of cultivated and 4.911 acres of uncultivated land, a total of 5.400 acres, all of which is to be acquired.

Note: Shaded portion of map is that which is to be acquired.

TAD DANFORD
Conveys all of the land situated within the Right of Way; said Right of Way extends 50.0 feet on each side of the center line of the Highway, except where otherwise noted; said Highway is located in the S. 1/4 of the S.E. 1/4 of Section 6, T.1 N., R.76 W., of the 6th Principal Meridian, more particularly described as follows:

Beginning at center line Station 60+55.6, a point on the South Section line of Section 6, whence the S.E. corner of Section 6 bears S.89°39'E. for 597.8 feet; thence along said Section line, S.89°39'E. for 51.7 feet; thence S.14°30'E. for 768.9 feet; thence S.75°30'E. for 30.0 feet; thence S.14°30'W. for 616.9 feet; to the South, East & West 1/16 line of Section 6; thence along said 1/16 line, S.89°45'E. for 165.4 feet; thence S.14°30'E. for 559.1 feet; thence S.75°30'E. for 30.0 feet; thence S.14°30'E. for 742.3 feet to the South Section line of Section 6; thence S.89°39'E. for 51.7 feet, to the point of beginning.

Said Right of Way contains 3.711 acres of uncultivated land, all of which is to be acquired.

Note: Shaded portion of map is that which is to be acquired.

TAD DANFORD


Conveys all of the land situated within the Right-of-Way; said Right-of-Way extends 50.0 feet on the left side, and 50.0 feet on the right side of the centerline of Highway; except where otherwise noted; said Highway is located in the NE $\frac{1}{4}$, SE $\frac{1}{4}$, Sec. 7, T-1-S, R-76-W of the 6th P.M., more particularly described as follows:

Beginning at centerline station 80 + 55.4, a point on the north, east and west section line of Sec. 7, whence along said section line, the northeast corner of Sec. 7 bears S 89°59'N for 597.8 feet; thence along said section line, N 85°59'W for 51.7 feet; thence S 14°30'E for 757.7 feet; thence S 76°30'W for 50.0 feet; thence S 14°30'E for 571.6 feet; thence on a curve to the right, with a radius of 1352.5 feet, for 188.6 feet to a point on the north, east and west 1/16 line of Sec. 7; thence along said 1/16 section line, S 89°47'N for 201.2 feet to the left Right-of-Way line, 100.0 feet from the centerline; thence along said Right-of-Way line on a curve to the left, with a radius of 1532.6 feet, for 237.2 feet; thence S 14°30'E for 571.6 feet; thence S 76°30'W for 50.0 feet; thence S 14°30'E for 731.1 feet to the north, east and west section line of Sec. 7; thence along said section line, N 89°59'W for 51.7 feet to the point of beginning.

Said Right-of-Way contains 4.386 acres of uncultivated land, all of which is to be acquired.

NOTE:

Shaded portion of map denotes land to be acquired.



Conveys all of the land situated within the Right-of-Way; said Right-of-Way extends 40.0 feet on the left side, and 100.0 feet on the right side of the centerline of the Highway; except where otherwise noted; said Highway is located in the NE $\frac{1}{4}$, SE $\frac{1}{4}$, Sec. 7, T-1-S, R-76-W of the 6th P.M., more particularly described as follows:

Beginning at centerline station 87 + 34, a point on the east and west 1/2 line of Sec. 7, whence the southeast corner of Sec. 7 bears S 0°08'N for 2618.1 feet; thence along said 1/2 section line, S 89°55'N for 43.1 feet; thence S 22°00'E for 634.2 feet; thence on a curve to the left, with a radius of 1472.5 feet, for 702.8 feet; thence S 84°29'N for 40.0 feet; thence on a curve to the left, with a radius of 1532.5 feet, for 7.1 feet to a point on the north, east and west 1/16 section line of Sec. 7; thence along said 1/16 line, N 89°47'N for 201.2 feet to a point on the right Right-of-Way line, 100.0 feet from centerline; thence along said Right-of-Way line on a curve to the right, with a radius of 1332.5 feet, for 662.8 feet; thence S 22°00'W for 490.8 feet to a point on the east and west 1/2 line of Sec. 7; thence along said 1/2 section line, S 89°55'N for 107.8 feet to the point of beginning.

Said Right-of-Way contains 4.358 acres of uncultivated land, all of which is to be acquired.

NOTE:

Shaded portion of map denotes land to be acquired.

Conveys all of the land situated within the Right-of-Way; said Right-of-Way extends 40.0 feet on the left side, and 100.0 feet on the right side of the centerline of the Highway; said Highway is located in the NE $\frac{1}{4}$, SE $\frac{1}{4}$, Sec. 7, T-1-S, R-76-W of the 6th P.M., more particularly described as follows:

Beginning at centerline station 87 + 34, a point on the east and west 1/2 line of Sec. 7, whence the southeast corner of Sec. 7 bears S 0°08'N for 2618.1 feet; thence along said 1/2 section line, N 89°55'W for 107.8 feet; thence S 22°00'W for 1414.8 feet to a point on the south, east and west 1/16 line of Sec. 7; thence along said 1/16 section line, N 89°59'N for 151.1 feet; thence S 22°00'N for 1415.9 feet, to a point on the east and west 1/2 section line of Sec. 7; thence along said 1/2 section line, N 89°55'W for 43.1 feet to the point of beginning.

Said Right-of-Way contains 4.543 acres of uncultivated land, all of which is to be acquired.

NOTE:

Shaded portion of map denotes land to be acquired.


Conveys all of the land situated within the Right-of-Way; said Right-of-Way extends 40.0 feet on the left side, and 100.0 feet on the right side of the centerline of the Highway; said Highway is located in the NE $\frac{1}{4}$, SE $\frac{1}{4}$, Sec. 7, T-1-S, R-76-W of the 6th P.M., more particularly described as follows:

Beginning at centerline station 115 + 58.2, a point on the south section line of Sec. 7, whence the southeast corner of Sec. 7 bears N 89°49'N for 1055.4 feet; thence along said section line, N 89°49'N for 43.2 feet; thence N 22°00'E for 1410.1 feet to a point on the south, east and west 1/16 line of Sec. 7; thence along said 1/16 section line, S 89°57'W for 151.1 feet; thence S 22°00'W for 1410.8 feet to a point on the south section line of Sec. 7; thence along said section line, N 89°49'N for 108.0 feet to the point of beginning.

Said Right-of-Way contains 4.553 acres, of which, 2.798 acres are cultivated and 1.755 acres are uncultivated land, all of which is to be acquired.

NOTE:

Shaded portion of map denotes land to be acquired.



R.W. LINKS

Conveys all of the land situated within the Right-of-way; said Right-of-way extends 40.0 feet on the left side, and 100.0 feet on the right side of the centerline of the Highway; said Highway is located in the NW 1/4, Sec. 18, T-1-N, R-76-W of the 6th P.M., more particularly described as follows:

Beginning at centerline station 115 + 68.2, a point on the north section line of Sec. 18, whence the northeast section corner of Sec. 18 bears N 89°49'W along said section line for 1085.4 feet; thence along said section line, S 89°49'W for 108 feet; thence S 22°00'W for 378.8 feet to the east, north and south 1/16 line of Sec. 18; thence along said 1/16 line, S 10°39'W for 711.4 feet; thence S 22°00'W for 47.6 feet to the north, east and west 1/16 line of Sec. 18; thence S 89°57'W along said 1/16 line for 43.2 feet to the point of beginning.

Said Right-of-way contains 3.063 acres of cultivated land to be acquired.

NOTE:
Shaded portion of map denotes land to be acquired.

GLADYS FOX SELLER

Conveys all of the land situated within the Right-of-way; said Right-of-way extends 40 feet on the left side and 60 feet on the right side of the centerline of the Highway; said Highway Right-of-way is the above width except where otherwise noted; said Highway is located in the NW 1/4, Sec. 18, T-1-N, R-76-W of the 6th P.M., more particularly described as follows:

Beginning at centerline station 129 + 36, a point on the north, east and west 1/16 line of Sec. 18, whence the northeast section corner of Sec. 18 bears N 89°49'W for 207.4 feet; thence along said 1/16 line, S 89°57'W for 107.9 feet; thence S 22°00'W for 325.5 feet; thence S 68°00'W for 40 feet; thence S 22°00'W for 1043.1 feet to the east and west 1/16 line of Sec. 18; thence along said 1/16 line, S 89°58'W for 107.8 feet; thence S 22°00'W for 138.5 feet, to the north, east and west 1/16 line of Sec. 18; thence along said 1/16 line, S 89°57'W for 43.2 feet to the point of beginning.

Said Right-of-way contains 3.479 acres; of which 0.020 acre is contained within the Right-of-way of the present road; 1.819 acres are cultivated land, and 1.640 acres, uncultivated land; a total of 3.459 acres to be acquired.

NOTE:
Shaded portion of map denotes land to be acquired.

F.W. LINKS

Conveys all of the land situated within the Right-of-way; said Right-of-way extends 40 feet on the left side and 60 feet on the right side of the centerline of the Highway, except where otherwise noted; said Highway is located in the NW 1/4, Sec. 18, T-1-N, R-76-W of the 6th P.M., more particularly described as follows:

Beginning at centerline station 156 + 98, a point on the south, east and west 1/16 line of Sec. 18, whence the south 1/2 corner of Sec. 18 bears S 28°04'W for 155.8 feet; thence along said 1/16 line, S 89°47'W for 55.8 feet; thence S 22°00'W for 378 feet; thence S 68°00'W for 10 feet; thence S 22°00'W for 997.1 feet; to the east and west 1/16 line of Sec. 18; thence S 89°55'W for 107.8 feet; thence S 22°00'W for 956.9 feet; thence S 68°00'W for 90 feet; thence S 22°00'W for 405.7 feet; thence on a curve to the left, with a radius of 1582.5 feet, for 54.8 feet to the south, east and west 1/16 line; thence S 89°47'W along said 1/16 line for 161.5 feet to the point of beginning.

Said Right-of-way contains 4.162 acres of uncultivated land, of which 0.344 acre is contained within the Right-of-way of the present road, leaving a balance of 3.818 acres to be acquired.

NOTE:
Shaded portion of map denotes land to be acquired.

G.W. & ANNA P. FYLE

Convey all of the land situated within the Right-of-way; said Right-of-way extends 60 feet on the left side and 100 feet on the right side of the centerline of the Highway, except where otherwise noted; said Highway is located in the NW 1/4, Sec. 18, T-1-N, R-76-W of the 6th P.M., more particularly described as follows:


Beginning at centerline station 156 + 98, a point on the south, east and west 1/16 line of Sec. 18, whence the south 1/2 corner of Sec. 18 bears S 28°04'W for 155.8 feet; thence along said 1/16 line, S 89°47'W for 52.8 feet; thence S 22°00'W for 25.7 feet; thence on a curve to the left, with a radius of 1582.5 feet, for 54.8 feet; thence S 1°16'W for 767.1 feet to the south, east and west section line of Sec. 18; thence along said section line, S 89°59'W for 180 feet; thence S 1°16'W for 691.5 feet; thence S 88°44'W for 50 feet; thence on a curve to the right with a radius of 1582.5 feet, for 518.4 feet; to a point on the south, east and west 1/16 line of Sec. 18; thence along said 1/16 line, S 89°47'W for 161.5 feet to the point of beginning.

Said Right-of-way contains 5.133 acres of uncultivated land, of which 0.993 acre is contained in the Right-of-way of the present road, leaving a balance of 4.140 acres to be acquired.

NOTE:
Shaded portion of map denotes land to be acquired.

SE 1/4, Sec 18, T.1N., R.76W of 6th P.M.
LINKEY (OWNER)

COLORADO STATE HIGHWAY DEPARTMENT
FEDERAL AID PROJECT No. 151-C
RIGHT-OF-WAY REVISED DEC. 14, '34



Conveys all of the land situated within that part of the present Right-of-way of the Highway which lies between the present 150 ft. R.O.W. line on the right and a line 10.0 feet on the right of, and parallel to, the Centerline of State Highway No. 2, except where otherwise noted. Said Highway is located in the SE 1/4 of Sec. 18, T.1 N., R.76 W of the 6th P.M. More particularly described as follows:

Beginning at a point on the west R.O.W. line of the Highway, whence Centerline Station 163+00.0 bears S 68°00'E for 60.0 feet, and whence the NW corner of Sec. 18 bears N 36°04'E for 4268.2 feet; thence along the present R.O.W. line of the Highway, N 68°00'E for 90.0 feet; thence S 22°00'W for 408.7 feet; thence on a curve to the left, with a radius of 1882.5 feet, for 872.6 feet; thence S 1°16'W for 6.3 feet; thence S 85°44'E for 100.0 feet; thence N 38°45'W for 18.6 feet; thence N 12°15'W for 312.4 feet; thence N 22°00'E for 650.0 feet, to the point of beginning.


thence N 1°16'W for 77.0 feet;

Said part of Right-of-way contains 1.982 acres.

T1N. R.76W of the 6th PM
Section 18

T1N. R.76W of the 6th PM
Section 19

Colorado State Highway Dept.
Project No. 151-C
Right of Way Map No. 5



F.W. LINE

Conveys all of the land situated within the Right-of-Way; said Right-of-Way extends 60.0 feet on left side, and 100.0 feet on the right side, of the centerline of the Highway; said Highway is located in the SW 1/4, Sec. 19, T-1-N, R-76-W of 6th P.M., more particularly described as follows:

Beginning at centerline station 169+89.9, a point on the north section line of Sec. 19, whence the north 1/4 corner of Sec. 19 bears N 89°39'W for 170.7 feet; thence along said section line S 89°39'W for 50.0 feet; thence S 1°16'W for 163.6 feet; thence S 1°19'W for 849.1 feet; thence on a curve right, with a radius of 2915.0 feet, for 294.0 feet to the north, east and west 1/16 line of section 19; thence along said 1/16 line, N 89°49'W for 164.0 feet; thence on a curve to the left, with a radius of 2765.0 feet, for 295.0 feet; thence N 1°19'W for 849.1 feet; thence N 1°16'W for 161.4 feet to the north section line of Sec. 19; thence along said section line, S 89°39'W for 100.0 feet to the point of beginning.

Said Right-of-Way contains 4.803 acres, of which 1.061 acres are contained within the Right-of-Way of the present road, leaving a balance of 3.452 acres of uncultivated land to be acquired.

NOTE: Shaded portion of map denotes land to be acquired.

J.P. & E. PER

Convey all of the land situated within the Right-of-Way; said Right-of-Way extends 50.0 feet on the left, and 100.0 feet on the right side of the centerline of the Highway; said Highway is located in the SW 1/4, Sec. 19, T-1-N, R-76-W of 6th P.M., more particularly described as follows:

Beginning at a point on the north and south 1/4 line of Sec. 19, whence the north 1/4 corner of Sec. 19 bears N 4°52'W along said 1/4 line for 3960.0 feet; thence along said 1/4 line, N 6°52'W for 96.0 feet; thence on a curve to the right, with a radius of 2965.0 feet, for 295.0 feet; thence N 27°58'W for 1221.4 feet; thence on a curve to the left, with a radius of 2765.0 feet, for 299.0 feet, to the north, east and west 1/16 line of Sec. 19; thence along said 1/16 line, S 89°49'W for 164.0 feet; thence on a curve to the right, with a radius of 2915.0 feet, for 294.0 feet; thence S 27°58'W for 1221.4 feet; thence on a curve to the left, with a radius of 2765.0 feet, for 295.0 feet; thence N 27°58'W for 1221.4 feet, to the north and south 1/4 line of Sec. 19; thence along said 1/4 line, N 4°52'W for 96.0 feet to the point of beginning.

Said Right-of-Way contains 10.148 acres of land, of which, 1.816 acres are contained within the Right-of-Way of the present road, leaving a balance of 8.232 acres of cultivated and 3.092 acres of uncultivated land, a total of 8.324 acres to be acquired.

NOTE: Shaded portion of map denotes land to be acquired.

ADALI W. YORK

Conveys all of the land situated within the Right-of-Way; said Right-of-Way extends 100.0 feet on the right side of the centerline of the Highway; said Highway is located in the SW 1/4, Sec. 19, T-1-N, R-76-W of the 6th P.M., more particularly described as follows:

Beginning at a point on the north and south 1/4 line of Sec. 19, whence the north 1/4 corner of Sec. 19, bears N 4°52'W along said 1/4 line for 3960.0 feet; thence along said 1/4 line, N 6°52'W for 96.0 feet; thence on a curve to the left, with a radius of 2965.0 feet, for 295.0 feet, to the south, east and west 1/16 line of Sec. 19; thence along said 1/16 line, N 89°49'W for 164.0 feet to the point of beginning.

Said Right-of-Way contains 0.019 acre of uncultivated land, all of which is to be acquired.

NOTE: Shaded portion of map denotes land to be acquired.


ED A. GREEN

Conveys all of the land situated within the Right-of-Way; said Right-of-Way extends 100.0 feet on the right side of the centerline of the Highway; said Highway is located in the SW 1/4, Sec. 19, T-1-N, R-76-W of the 6th P.M., more particularly described as follows:

Beginning at a point on the north and south 1/4 line of Sec. 19, whence the north 1/4 corner of Sec. 19, bears N 4°52'W along said 1/4 line for 3960.0 feet; thence along said 1/4 line, N 6°52'W for 96.0 feet; thence on a curve to the right, with a radius of 2965.0 feet, for 295.0 feet, to the south, east and west 1/16 line of Sec. 19; thence along said 1/16 line, N 89°49'W for 164.0 feet to the point of beginning.

Said Right-of-Way contains 0.046 acre of uncultivated land, all of which is to be acquired.

NOTE: Shaded portion of map denotes land to be acquired.



Conveys all of the land situated within the Right of Way; said Right of Way extends 80.0 feet on each side of the centerline of the Highway; said Highway is located in the N.W. 1/4 of the N.E. 1/4, and the N.E. 1/4 of the N.W. 1/4, all in Section 6, T.1 N., R.76 W. of the 6th Principal Meridian, more particularly described as follows:

Said Right of Way contains 0.545 acres, all of which is to be acquired.

Note: Shaded portion of map is that which is to be acquired.