

987

INDEX OF SHEETS

SHEET NO.'S	
1	SKETCH MAP AND TITLE PAGE
2	TYPICAL SECTION, SURFACING PLAN, AND TABULATION OF LENGTH
3	SUMMARY OF QUANTITIES, SEL. BORROW PLAN & LIST OF GUARD POSTS
4-11	DETAILS OF BRIDGE, STA. 1038 +
12	TYPICAL STANDARD NAME PLATE
13	STANDARD LETTERS & FIGURES FOR YEAR & STRUCTURE NUMBERS
14	STANDARD TIMBER GUARD POSTS
15	STANDARD METHODS FOR SUPERELEVATION & WIDENING OF CURVES
16	STANDARD TYPICAL SIDE APPROACH ROADS, FLARING, CUT SLOPE TREATMENT AND WIDENING AT BRIDGES
17	STANDARD ROADWAY CONSTRUCTION TRAFFIC SIGNS
18	ALIGNMENT PLAN AND PROFILE
19-23	ROADWAY CROSS SECTIONS
23	SUMMARY OF EARTHWORK QUANTITIES, AND MASS DIAGRAM


COLORADO STATE HIGHWAY DEPARTMENT PLAN AND PROFILE OF PROPOSED FEDERAL AID PROJECT NO. F 92 (2) STATE HIGHWAY NO. 6 50 PUEBLO COUNTY

SCALES OF ORIGINAL TRACINGS
 ON PLAN 1 IN. = 100 FT.
 ON PROFILE 1 IN. = 100 FT. HORIZONTAL
 1 IN. = 10 FT. VERTICAL
 GRADE LINE ON PROFILE IS SHOWN AS GRADE OF FINISHED ROAD
 GROSS LENGTH OF PROJECT 9811 FEET = 0.185 MILES
 NET LENGTH OF PROJECT 480.2 FEET = 0.090 MILES


FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
3	COLO.	F 92 (2)	1	

REV. ENDS OF PROJECT AND LENGTH 7/2/47-E.E.C.

CONVENTIONAL SIGNS
 CENTER LINE OF SURVEY
 RIGHT OF WAY LINES
 TOWNSHIP LINES
 SECTION LINES
 ONE QUARTER SECTION LINES
 BARBED WIRE FENCE
 POLE LINES



Dr. 20



NOTICE TO BIDDERS
 It is recommended that bidders on this Project go over the plan details with the following Field Representative of the Department.
 George N. Miles, Division Engineer, Pueblo.

RECOMMENDED FOR APPROVAL
 J. Bell
 ASSISTANT ENGINEER
 DATE 5-16-47

APPROVED
 M. C. Waters
 STATE HIGHWAY ENGINEER
 DATE 5-16-47

RECOMMENDED FOR APPROVAL
 DISTRICT ENGINEER
 PUBLIC ROADS ADMINISTRATION
 FEDERAL WORKS AGENCY
 DATE

APPROVED
 DIVISION ENGINEER
 PUBLIC ROADS ADMINISTRATION
 FEDERAL WORKS AGENCY
 DATE

NOTE-


See Standard M-2-C for details of Cut Slope Treatment, flaring & widening for guard fence and/or guard posts.

The depth & width of side ditch shall be varied where necessary, in order to provide proper drainage and/or entrance to drainage structures.

Earth Slope
SL 10:1
SL to suit Material

Excavation or Borrow below the 6:1 Slope and/or 10:1 Slope will not be permitted

TYPICAL CROSS SECTION OF IMPROVEMENT



6" Compacted thickness of Gravel or Crushed Rock Surfacing is to be placed in two courses at the following approximate rates per 100 linear feet of Roadway.

STATIONS	COURSES	
	2" TOP	4" BOTTOM
1036+00 - 1038+52 Back (Roadway)	41	89
1038+70.9 Ahead - 1043+10.6 (Bridge)	32	28
	(30' wide)	(13' wide)
1043+10.6 - 1046+00 (Roadway)	41	89

* See Bridge Sheet No. 4 for widening of Surfacing on Bridge.

The upper 12" portion of subgrade is to be constructed of Selected Borrow at locations designated in Selected Borrow Tabulation. Estimated quantities involved in this operation and thickness of material required are tabulated on Sheet No. 3.

FILL SLOPES

ON TANGENT:
6:1 where "H" is less than 3 ft
2:1 where "H" is over 3 ft

GENERAL NOTES

This Project is to be constructed in conformity with the Standard Specifications of the Colorado State Highway Department adopted June 1, 1940.

All quantities on preliminary plans are to be considered approximate only.

All Roadway Excavation required to construct this Project is to be obtained as indicated on the plans. Quantities involved beyond the limits of the ditch, as shown on the Typical Section, either noted on the Profile as "Borrow" or on the List of Structures as "Embankment", are to be classified and paid for as "Unclassified Excavation". These quantities are to be staked as part of the original Excavation at locations indicated on the plans. Slope stakes, beyond the limits of the Typical Section as shown, are subject to change by the Engineer to fit conditions actually met in construction.

All poles encroaching on construction are to be moved by the owners.

Except as otherwise noted on the plans, payment for Overhaul will be based on measurement along the center line of the Project.

The entire Project shall be cleared in conformity with the requirements of the Standard Specifications except that such trees or shrubs as the Engineer may designate, shall be left in place and protected from damage during construction operations.

All Curves are to be Superelevated as provided by the Standard Superelevation sheet included with the plans.

The Detour for this Project lies along the present traveled road. At all places on the Project where the new work lies along the present traveled road, the Contractor shall, at his own expense, prosecute construction in such manner that traffic may readily pass over the road & bridge. Also, the Contractor shall maintain, in safe condition and at his own expense, all temporary approaches to and crossings of intersecting roads.

All Concrete on this Project shall be air entrained Concrete.

SURFACING PLAN

It is estimated that material for Gravel Surfacing for the Project is available in the vicinity of the Pit indicated in the following Tabulation. Estimated quantities involved in this operation, are shown below.

Alteration of the Surfacing Plan as here outlined, will be allowed only on written permission from the Department.

MATERIAL TO BE PLACED	SOURCE	TONS AVAILABLE	TONS		USED		OVERHAUL TON MILE
			ROADWAY		BRIDGE		
			TOP COURSE	BOTTOM COURSE	TOP COURSE	BOTTOM COURSE	
1036+00 To 1038+26.3 1038+26.3 To 1038+52 BK. 1038+70.9 And To 1043+106 1043+106 To 1043+25.4 1043+25.4 To 1046+00 ROAD APPROACH WIDENING SHOULDERS 1032+00 To 1036+00 } 1046+00 To 1048+00 }	200' NE of the East End of Bridge in the NE 4 of NW 4, Sec 17, 8 NE 4 of NE 4, Sec 18, T 21 S, R 61 W.	AMPLE	93	202	11 141 6	23 124 14	F.H. F.H. F.H.
			113 82	245 178			F.H.
			28	52			F.H.
SUB-TOTALS			316	677	158	161	
TOTALS			993		319		Free Haul

TABULATION OF LENGTH & DESIGN DATA

STATION	ROADWAY LIN. FT.	BRIDGES		NON FED. AID ROADWAY LIN. FT.
		LIN. FT.	LOADING	
1036+00 Beg. (Non-Port)				226.3
1038+26.3 Begin F 92(2)	25.7			
= 0+00 Begin FAP 92				
1038+52.0 Back =				
EQUATION				
1038 + 70.9 Ahead				
Huerfano River Bridge	439.7	H-20		
1043+10.6	14.8			
1043+25.4 End F 92(2)				274.6
= 4+80.2 End F.A.P. 92				
1046+00 End (Non-Port)				
TOTALS	40.5	439.7		500.9
SUMMARY				
F 92(2) Roadway				40.5 0.007
F 92(2) Bridges				439.7 0.083
TOTAL F 92(2) (Fed. Aid)				480.2 0.090
F 92(2) Approaches (Non-Fed. Aid)				500.9 0.095
TOTAL F 92(2)				981.1 0.185
DESIGN DATA				
Maximum Degree of Curve				1°
Maximum Grade				2.204 %
Minimum N.P.S.D. - horizontal				over 900'
Minimum N.P.S.D. - vertical				540'
Maximum Design Speed				50 M.P.H.

FED. ROAD DIST. NO.	STATE	PROJ. NO.	SHEET NO.	TOTAL SHEETS
3	COLO.	F 92 (2)	3	

REV. SUMMARY FOR NON-FED AID QUANTITIES 7/2/47, E.E.O.

TIMBER GUARD POSTS

STATION	SIDE	SPACING	NUMBER	
			REMOVE & RESET	NEW
1043 + 14 To 1043 + 25	R. & L.	Bridge		6
1043 + 25 To 1043 + 78	R. & L.	Bridge		# 4
1034 + 90 To 1038 + 26	R. & L.	Standard	# 27	
1038 + 26 To 1038 + 50	R. & L.	Standard	8	
TOTALS			# 27 8	# 4 6

QUANTITIES SO MARKED ARE NON-FEDERAL AID.

*SELECTED BORROW PLAN

It is estimated that material for Selected Borrow for the project is available in the vicinity of the pit indicated in the following tabulation. Estimated quantities involved in this operation are shown below. No alterations of the Selected Borrow Plan as here outlined will be allowed without written permission from the Department.

MATERIAL TO BE PLACED	AVAILABLE	SOURCE	CU. YDS. USED	OVERHAUL STA. YDS.
1043 + 11 To 1043 + 25	AMPLE	200' NE of the East End of Bridge in the NE 1/4 of NW 1/4 Sec. 17 & NE 1/4 of NE 1/4 Sec. 18, T21S, R61W.	26	F. H.
1043 + 25 To 1045 + 00			# 324	F. H.
TOTALS			# 324 26	Free Haul

* Selected Borrow Material is to be classified and paid for as "Unclassified Excavation". Included in quantities on "Summary of Earthwork Quantities" sheet.






SUMMARY OF APPROXIMATE QUANTITIES

ITEM NO.	ITEM	UNIT	FED. AID		NON FED. AID APPROACHES	PROJECT TOTALS
			ROADWAY	BRIDGE STA. 1038+		
10a	Clearing & Grubbing entire Project	Lump Sum				
11x	Removal of parts of Present Structure, Sta 1038+	" "				
11y	Remove & Reset Name Plate	" "				
11c	Remove & Reset Guard Posts	Each	8		27	35
13c	Unclassified Excavation	Cu Yd	100		2900	3000
14a	Dry Rock Excavation (Structural)	Cu Yd		180		180
14b	Dry Common Excavation	" "		220		220
14c	Wet Rock Excavation	" "		150		150
14d	Wet Common Excavation	" "		500		500
15a	Rolling Embankments & Cuts	Unit Hr	10		20	30
15b	Furnishing Roller	Roller Unit	0.3		1.7	2
15c	Wetting Embankments & Cuts	M Gal	15		85	100
15d	Rolling with Finishing Roller	Roller Hour	3		7	10
15e	Furnishing Finishing Roller	Lump Sum	Prorated		Prorated	
15y	Selected Backfill	Cu Yd		2160		2160
18a	Station Yard Overhaul	Sta-Yd	100		3900	4000
26a	Gravel or Crushed Rock Surfacing	Ton	100	300	1000	1400
44b	Miscellaneous Treated Timber	M ft bm		0.6		0.6
46a	Class 'A' Concrete	Cu Yd		1168		1168
46r	Class 'A' Concrete (Handrails)	" "		37		37
47	Reinforcing Steel	Lb		101,200		101,200
60a	Treated Timber Piling	Lin Ft		960		960
66	Rip Rap enclosed in wire netting	Cu Yd		180		180
79b	Membrane Water-proofing (2 Ply)	Sq Yd		102		102
80b	Bronze Name Plates	Each		2		2
89a	Drain Pipe (Concrete Floor) (4"x4'-6")	Each		16		16
92	Timber Guard Posts	Each	6		4	10

REVISIONS

Rev. 5-8-44 L.M.R. Added Dowels W. Curb/Dia. Date
Rev. 6-8-45 G.R.B. Changed Dowels to Anchors

PROJECT NO. 3 STATE COLO. F.A. Proj. F-92-12 SHEET 4



**REINFORCEMENT BAR LIST
EAST & WEST HANDRAILS & W. CURB**

MARK	SIZE	NO.	LENGTH	TYPE	DIMENSIONS	BENDING DIAGRAMS
			ft		ft m	
H1	1/2"	20	4'-6"	Str.		 TYPE I
H2	1/2"	20	7'-8"	"		
H3	1/2"	80	11'-8"	"		
H4	1/2"	200	2'-8"	"		
H5	1/2"	80	13'-2"	"		
H6	1/2"	40	16'-2"	"		 TYPE II
H7	1/2"	40	6'-2"	"		
H8	1/2"	594	7'-0"	I		
S1	3/8"	60	40'-0"	Str.	2'-0" 2'-0"	 TYPE III
S2	3/8"	415	4'-4"	Str.	2'-0" 2'-0"	
S3	3/8"	10	13'-6"	Str.	1'-3" 2'-0"	
S4	3/8"	28	6'-0"	Str.		
S5	3/8"	32	5'-6"	Str.		

BAR SUMMARY

78/5 Lin. Ft. 1/2" @ 0.668 = 5220 Lb.
4750 Lin. 3/8" @ 1.043 = 4954 Lb.
+ 1% Overrun 106 Lb.
TOTAL = 10,280 Lb.

GENERAL NOTES
All work shall be done according to the standard specifications of the Colorado State Highway Department adopted June 1, 1940. All concrete shall be Class "A".
Forms for concrete surface exposed in the finished work shall be constructed of shiplap or tongue and groove lumber 3/4" S.S. unless faced with panel board.
All reinforcing bars shall be deformed, intermediate grade steel tagged with station number and designation. Main bars shall not be spliced.
Soundings and depth of footings shown are according to the best available data. If essentially different conditions are encountered the Bridge Engineer will inspect and determine if redesign is necessary.

SUMMARY OF QUANTITIES FOR ENTIRE STRUCTURE

ITEM No.	DESCRIPTION	UNIT	ARCHES	EAST SPAN-DREL WALL	ABUT. No. 6	PIERS No. 2, 3, 4 & 5	ABUT. No. 1	E & W HANDRAILS & W. CURB	ROCK FILLED BULKHEAD	TOTAL
11x	Removal of Parts of Present Structure	"								Lump Sum
14a	Dry Rock Excavation (Str.)	Cu. Yd.		180						180
14b	Dry Comm.	"		10						220
14c	Wet Rock	"		90						150
14d	Wet Comm.	"								90
15y	Selected Backfill	Cu. Yd.	1450		350	150	210			2,160
44b	Miscellaneous Treated Timber	M. Ft. - B.M.							0.530	0.530
44b	Class "A" Concrete	Cu. Yd.	408	199	109	202	190	60		1,168
46r	Class "A" Concrete (Handrails)	Cu. Yd.						37		37
47	Reinforcing Steel	Lb.	61,920	16,940	5,610		6410	10,280		101,160
60a	Treated Timber Piling	Lin. Ft.							960	960
66	Rip Rap Enclosed in Wire Netting	Cu. Yd.							180	180
79b	Membrane Waterproofing (2 Ply)	Sq. Yd.	94							102
80b	Brass Name Plate	Ea.								2
11y	Remove & Reset Name Plate	Lump Sum								Lump Sum
89a	Drain Pipe (Concrete Floor) (4x4x6)	Ea.				16				16
†	Cinch Anchors 3/8"	Ea.				100		116		216
†	Tie Rods 1/2"	Ea.	40							40
†	Expansion Joint Material	Sq. Ft.		210						210
†	To be included in bid price of Class "A" Concr.	See Schedule	on Sheet # 5	For places Req'd.						

REFERENCE DRAWINGS
Sheet No. 5 General Layout and Details.
" 6 Spandrel Wall and Details.
" 7 Arch Construction & Reinforcement.
" 8 New Construction at Abut. No. 6.
" 9 New Construction at Abut. No. 1.
" 10 New Construction at Abut. No. 1 and order of pour for arch ribs.
" 11 Details of Rockfilled Bulkhead and Nameplate.

DESIGN DATA
A.A.S.H.O. 1941-H-20
Fs 18,000 #/in²
Fc 633 #/in²

**COLORADO
STATE HIGHWAY DEPARTMENT**

**SUMMARY OF QUANTITIES
HANDRAIL DETAILS
AND REINF. BAR LIST**

Across **HUERFANO RIVER**
Sta. 1045+35.5 to 1058+70.9
Near 800th St. 1/4 mi. S.E. of B.M.
Designed by L.M.R. Approved by G.R.B.
Made by L.M.R. Bridge Engineer
Checked by A.L.C. Date: Jan. 20, 1947.

† To be included in bid price of Class "A" Concrete

STRUCTURE NO. L-19-B







REVISIONS

Rev. 5-18-44 L.M.R. Spec. type of joint filler; added counterfort key.

REV. NO.	DATE	STATE	FAPROJ.	SHEET NO.	TOTAL SHEETS
3		COLO.	F-92-2	5	

PIECES OF 1" EXPANSION MATERIAL FOR THIS REQUIRED 210.56 FT.		
LOCATION	SIZE	LENGTH
Abut. #5 & 6	2	1" x 12" x 11'-8"
	2	1" x 4" x 11'-8"
Pier #5 & 6	2	1" x 12" x 12'-5"
	2	1" x 4" x 12'-5"
Pier #4 & 5	2	1" x 12" x 11'-11"
	2	1" x 4" x 11'-11"
	2	1" x 12" x 12'-3"
	2	1" x 4" x 12'-3"
East Curb	10	1" x 18" x 2'-7"
	10	1" x 18" x 0'-7 3/4"


* Expansion Joint Material to be Fiber Type. (Asphalt Shipped by road 20% by wt.)



COLORADO
STATE HIGHWAY DEPARTMENT
GENERAL LAYOUT & DETAILS
BRIDGE WIDENING

Address: HUERFANO RIVER
Sta. 1043+10.25 to 1043+15.3
Near BOONE Sec. 18 T. 25 S. R. 61 W.

Designed by A.L.C. Approved by J.P. of Boone
Made by L.M.R. Bridge Engineer
Checked by Date: Jan. 20, 1947.




COLORADO
STATE HIGHWAY DEPARTMENT

SPANDREL WALL & DETAILS
FOR
BRIDGE WIDENING

Across HUERFANO RIVER
Sta. 1043 + 10.00 to 1038 + 70.0
Near BOONE Sec. 18 T. 21S. R. 61W.


Designed by A.L.C. Approved by P. G. Bailey
Made by Bridge Engineer
Checked by Date: Jan. 20 1947.

1. ALC
 2. ALC
 3. ALC
 4. ALC
 5. ALC
 6. ALC
 7. ALC
 8. ALC
 9. ALC
 10. ALC
 11. ALC
 12. ALC
 13. ALC
 14. ALC
 15. ALC
 16. ALC
 17. ALC
 18. ALC
 19. ALC
 20. ALC
 21. ALC
 22. ALC
 23. ALC
 24. ALC
 25. ALC
 26. ALC
 27. ALC
 28. ALC
 29. ALC
 30. ALC
 31. ALC
 32. ALC
 33. ALC
 34. ALC
 35. ALC
 36. ALC
 37. ALC
 38. ALC
 39. ALC
 40. ALC
 41. ALC
 42. ALC
 43. ALC
 44. ALC
 45. ALC
 46. ALC
 47. ALC
 48. ALC
 49. ALC
 50. ALC
 51. ALC
 52. ALC
 53. ALC
 54. ALC
 55. ALC
 56. ALC
 57. ALC
 58. ALC
 59. ALC
 60. ALC
 61. ALC
 62. ALC
 63. ALC
 64. ALC
 65. ALC
 66. ALC
 67. ALC
 68. ALC
 69. ALC
 70. ALC
 71. ALC
 72. ALC
 73. ALC
 74. ALC
 75. ALC
 76. ALC
 77. ALC
 78. ALC
 79. ALC
 80. ALC
 81. ALC
 82. ALC
 83. ALC
 84. ALC
 85. ALC
 86. ALC
 87. ALC
 88. ALC
 89. ALC
 90. ALC
 91. ALC
 92. ALC
 93. ALC
 94. ALC
 95. ALC
 96. ALC
 97. ALC
 98. ALC
 99. ALC
 100. ALC



COLORADO
STATE HIGHWAY DEPARTMENT
 ARCH CONSTRUCTION
 AND REINFORCEMENT
 Across: HUERFANO RIVER
 Sta. 1043+10.65 to 1038+70.9
 Near: BOONE Sec. 18, T. 21 S. R. 6 W.
 Designed by ALC Approved by *W. J. Bailey*
 Made by ALC Bridge Engineer
 Checked by GRB Date: Jan. 20, 1947.









Initial	Rev
ALC	5-44
GRB	5-17-44
GRB	6-10-44
ALC	6-12-44



COLORADO
STATE HIGHWAY DEPARTMENT
NEW CONSTRUCTION
AT ABUTMENT NO. 6



Across HUERFANO RIVER
Sta. 1043+10.65 to 1038+70.9
Near BOONE Sec. 18 T.21S. R.61W.

Designed by ALC Approved by G.R.B.
Made by G.R.B. Bridge Engineer
Checked by G.R.B. Date: Jan. 20, 1947




COLORADO
STATE HIGHWAY DEPARTMENT
 NEW CONSTRUCTION AT
 ABUTMENT NO. I
 FOR WIDENING
ACROSS HUERFANO RIVER
 Sta. 1043+10.65 to 1038+70.9
 Near BOONE Sec. 18 T.21S. R.61W

Designed by ALC	Approved by <i>G. D. Baskin</i>
Made by GRB	Bridge Engineer
Checked by	Date: Jan. 20, 1947.



BAR LIST FOR ABUTMENT NO. I



MARK	SIZE	NO REQD	LENGTH	TYPE	2	m	r	t		MARK	SIZE	NO REQD	LENGTH	TYPE	2	m	r	t		BENDING DIAGRAMS	ORI VAL	
E ₁	1" ø	7	12'-0"	Str						E ₁₃	1" ø	16	11'-2"	Str								
E ₂	1" ø	7	12'-0"	Str						E ₁₄	1" ø	4	13'-3"	Str								
E ₃	1" ø	7	14'-8"	Str						E ₁₅	1" ø	4	14'-9"	Str								
E ₄	½" ø	18	7'-3"	Str						E ₁₆	1" ø	4	16'-0"	Str								
E ₅	¾" ø	24	22'-0"	Str						E ₁₇	1" ø	5	18'-6"	Str								
E ₆	¾" ø	18	25'-0"	Str						E ₁₈	½" ø	14	19'-8"	III	16'-6"	3'-2"						
E ₇	¾" ø	13	23'-6"	Str						E ₁₉	½" ø	2	8'-5"	III	5'-3"	3'-2"						
E ₈	¾" ø	16	11'-6"	Str						E ₂₀	½" ø	1	13'-8"	III	7'-9"	3'-2"						
E ₉	¾" ø	24	9'-2"	III						E ₂₁	½" ø	1	10'-3"	III	10'-6"	3'-2"						
E ₁₀	¾" ø	18	22'-0"	Str						E ₂₂	½" ø	1	16'-8"	III	13'-6"	3'-2"						
E ₁₁	¾" ø	15	19'-6"	Str						S ₂₆	½" ø	8	4'-11"	IX								
E ₁₂	1" ø	17	8'-4"	Str						S ₂₇	¾" ø	7	7'-9"	Str								

STRUCTURE NO. L-19-B



COLORADO
STATE HIGHWAY DEPARTMENT
NEW CONSTRUCTION AT
ABUTMENT NO.1
FOR WIDENING

Across **HUERFANO RIVER**
Sta. 1043 + 1065 to 1038 + 70.9

Near BOONE	Sec. 18 T.21S. R. 61W
Designed by ALC	Approved by Rob. Bailey
Made by GRB	Bridge Engineer
Checked by	Date: Jan. 20, 1947.



NOTE:- Information to be as shown above. See Standard Sheet M-6-E, these plans, for other details.
One plate to be placed on each R.H. wing post.





GENERAL NOTES

All work shall be done according to the Standard Specifications of the Colorado State Highway Department adopted June 1, 1940.


Wire netting to be A.S. & W. Galv. Fencing, Specification "F" or equivalent.

Laps in netting shall be held together with No. 9 Galv. wire ties at not less than 12" Ctrs.

Wire netting must NOT be fastened to piles or longitudinal tie wires.



AT END OF WEST WING OF ABUT. No. 4



PART ELEVATION ~ ROCKFILLED BULKHEAD
OFF WING ENDS OF ABUT. No. 1

SUMMARY OF QUANTITIES FOR ROCKFILLED BULKHEAD			
ITEM No.	DESCRIPTION	UNIT	TOTAL
14b	Dry Common Excavation (Str.)	Cu. Yd.	40
14d	Wet " "	"	90
44b	Miscellaneous Treated Timber	M Ft. B. M.	0.530
60a	Treated Timber Piling	Lin. Ft.	360
66	Riprap Enclosed in Wire Netting *	Cu. Yd.	180


* INCLUDES:-
260 Lin. Ft. Wire Netting 42" width
1250 " " " " 58" "
30 3/4" Galv. bolts, 21" @ 196# = 59#
60 C.I.Q.G. Washers @ .75# = 45#
100 Lin. Ft. Galv. wire No.9 = 59#
4 Cu.Yds. Hand Placed Rock Fill

STRUCTURE NO. L-19-B

COLORADO
STATE HIGHWAY DEPARTMENT
DETAILS AND SUMMARY
OF
ROCKFILLED BULKHEAD
AND
NAMEPLATE
HUERFANO RIVER
Across
Sta. 1038+30
Near BOONE Sec. 16 T. 21S. R. 61W.
Designed by A.L.C. Approved by *A.L. Beck*
Made by A.L.C. & R. Bridge Engineer
Checked by L.M.R. Date: Jan. 20, 1947.

STANDARD M-6-E

FED. ROAD DIST. NO.	STATE	SHEET NO.	TOTAL SHEETS
3	COLO.	F92(4) 12	



BRONZE NAME PLATE
ITEM NO 80 b

GENERAL NOTES

ALL WORK SHALL BE DONE ACCORDING TO THE LATEST STANDARD SPECIFICATIONS OF THE COLORADO STATE HIGHWAY DEPARTMENT.

COLORADO STATE HIGHWAY DEPARTMENT TYPICAL STANDARD NAME PLATE			
Across	Sta.	Sec.	T. R.
Neat			
Designed by GKD	Approved by J. E. Bailey		
Made by J.E.R.	Bridge Engineer		
Checked by	Date: Sep 22 1940		

STRUCTURE NO.

REVISIONS

STANDARD M-10-B.

FED. ROAD DIST. NO.	STATE	PROJ. NO.	SHEET NO.	TOTAL SHEETS
3	COLO.	E-926	13	

1 2 3 4 5 6 7 8 9 0.

A B C D E F G H I J K L

M N O P Q R S T U V W

X Y Z I 1 4 K 1 9 4 0


Scale in Inches
0 1 2 3

SAMPLE BRIDGE NUMBER


SAMPLE YEAR NUMBER

GENERAL NOTES
ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS OF THE COLORADO STATE HIGHWAY DEPARTMENT, ADOPTED JUNE 1, 1940.
COMPENSATION FOR THIS WORK SHALL BE INCLUDED IN THE ORIGINAL CONTRACT ITEMS AND WILL NOT BE PAID FOR AS A SEPARATE ITEM.
THE SIZE, SHAPE AND SPACING OF THE LETTERS AND FIGURES SHALL BE IN ACCORDANCE WITH THE FULL SIZE SHOWN ON THIS SHEET.
ADDITIONAL COPIES OF THIS FULL SIZE SHEET CAN BE OBTAINED FROM THE DEPARTMENT WITHOUT CHARGE.
THE YEAR NUMBERS ARE RECESSED IN CONCRETE $\frac{3}{8}$ " MINIMUM AS SHOWN INTO THE PANEL OF THE ENDPOST ON THE RIGHT HAND SIDE OF EACH BRIDGE END AND INTO THE FACE OF THE DOWNSTREAM HEADWALL OF CULVERTS, SIPHONS, CATTLE PASSES, RETAINING WALL, ETC.
NUMBERS TO BE MADE OF WOOD METAL OR OTHER SUITABLE MATERIAL AND ATTACHED TO THE FORMS BEFORE CONCRETE IS POURED.
THE YEAR NUMBER OF EACH STRUCTURE SHALL CORRESPOND WITH THE YEAR IN WHICH THE CONCRETE IS POURED.
THE STRUCTURE NUMBER SHALL BE STENCILED ON THE RIGHT HAND SIDE OF EACH BRIDGE END AS SHOWN ON THIS STANDARD AND AS SPECIFIED.
THE CORRECT NUMBER FOR EACH BRIDGE IS SHOWN IN THE LOWER RIGHT HAND CORNER OF THE DETAIL SHEETS FOR THAT BRIDGE.
A PROPER WHITE BACKGROUND RECTANGULAR IN SHAPE AND EXTENDING THREE INCHES BEYOND THE LIMITS OF THE NUMBER SHALL BE PAINTED WITH TWO COATS OF ACCEPTABLE WHITE PAINT UNLESS AN APPROVED WHITE CONCRETE PAINT IS USED. BEFORE PAINTING THE SURFACE MUST BE THOROUGHLY DRIED, CLEANED AND PROPERLY SIZED. ON TIMBER HANDRAILS THE WHITE PAINT USED ON THE BRIDGE WILL BE SATISFACTORY.
AFTER THE WHITE BACKGROUND HAS DRIED SUFFICIENTLY, THE CORRECT STRUCTURE NUMBER SHALL BE CAREFULLY STENCILED ON IT, WITH TWO COATS OF STANDARD "C" SECOND FIELD COAT PAINT AS SPECIFIED UNDER ITEM 41, STEEL BRIDGES. THE BRACES OF THE STENCILED LETTERS AND FIGURES SHALL BE CAREFULLY FILLED IN BY HAND TO MAKE SOLID FIGURES.
SUFFICIENT TIME BETWEEN SUCCESSIVE COATS SHALL BE ALLOWED TO PERMIT THOROUGH DRYING.


SECTION



TYPICAL FOR CONCRETE ENDPOST



TYPICAL FOR TIMBER WING HANDRAIL



TYPICAL FOR CULVERT HEADWALL
SYPHON, RETAINING WALL, ETC.
(Downstream Headwall)

STANDARD M-10-B

STRUCTURE NO.


COLORADO
STATE HIGHWAY DEPARTMENT
STANDARD
LETTERS AND FIGURES
FOR
YEAR NUMBERS AND
STRUCTURE NUMBERS

Designed by G.H.D. Approved by *G.H.D.*
Made by W.P.M. Bridge Engineer
Checked by *W.P.M.* Date: *1 June, 1946*


REVISIONS

Rev. 11-24-39-P.B.B. Reflector Units (Min. 5' x 10').
 Rev. 10-19-39-P.B.B. Length and treatment of posts.
STANDARD M-19-B
 Rev. 6-28-40-A.Z. - 1940 Specs. & Location of posts.
 Rev. 10-9-40-P.B.B. - Painting & Ref. Units.
 Rev. 2-24-41-P.B.B. - Terminal Guard Post Placement.
 Rev. 7-2-41-P.B.B. - White Paint.
 Rev. 7-9-42-W.C.B. - Before Painting of Posts.
 Rev. 8-6-45 A.Z. - Location of posts.


FED. ROAD DIST. NO.	STATE	SHEET NO.	TOTAL SHEETS
3	COLO.	F-9261 14	



SHOWING PLACEMENT ON NORMAL ROADWAY FILLS



SHOWING PLACEMENT AT MINOR STRUCTURES



SHOWING PLACEMENT AT BRIDGE APPROACHES

TERMINAL GUARD POST
 NOTE: Terminal Guard Posts as detailed above to be used only for the near Post on the right side of, and facing, approaching traffic. All other Terminal Guard Posts to be identical with Intermediate Guard Posts.

GENERAL NOTES

- All work shall be done in accordance with the Standard Specifications of the Colorado State Highway Department applicable to the Project.
- All wood posts shall be made from seasoned, straight, sound Lodgepole Pine, Southern Yellow Pine, or West Coast Douglas Fir.
- No section of wood posts shall be less than 6" in diameter.
- All wood posts shall be entirely peeled and shored, thoroughly seasoned and dry, with square tops.
- All wood posts shall be set and tampered in plumb and firm, to the lines and grades as directed by the Engineer.
- Reflector Units in all posts shall be placed in such position that the units will function at a distance of 500 feet.
- On tangents the Reflector Units shall be placed at an angle of approximately five degrees to a line parallel to the centerline of the highway.
- In all instances a test shall be made to assure the position of the Reflector Units to be the most effective possible.
- The diameter of holes drilled in the posts shall be drilled approximately one-eighth (1/8) inch less than the diameter of the signal button base. In all instances the hole shall be enough undersize that the button when driven into the post shall have complete bond with the post and be securely locked in correct position.
- Posts shall be given a standard pressure Creosote treatment and then be thoroughly steam-cleaned in accordance with requirements of specifications.

COLORADO STATE HIGHWAY DEPARTMENT
STANDARD
TIMBER GUARD POSTS


Designed by R.E.L. Approved by [Signature]
 Made by P.B.B. Chief Engineer
 Checked by [Signature] Date: 7-15-1939

GENERAL DETAILS FOR FLARING OF EARTH CUTS, CUT SLOPE TREATMENT & WIDENING AT BRIDGES


STANDARD M-2-C

F&U. H&U. DIST. NO.	STATE	SHEET NO.	TOTAL SHEETS
3	COLO.	F-92(2) 16	
Rev. for 50' R. on Type II Rd. Appr. 3/5/46 JRL Rev. Gen'l. Notes - Appr. Surf. 4-5-46-A.Z. Rev. Type I Road Approach 7-31-46 JPK Rev. Guard Fence - Note 10-19-46 G.R.S. Rev. Decel. Dist. 60 M.P.H. to 300' R.O.W.			


TYPICAL PLANS FOR SIDE APPROACH ROADS



STANDARD CROWNED SECTION



SUPERELEVATED SECTIONS



GENERAL NOTES

All work shall be done in accordance with the Standard Specifications of the Colo. State Highway Dept. applicable to the Project.

All side approach roads to the Project shall be gravel surfaced with a 4 inch thickness of "Gravel or Crushed Rock Surfacing" extending approximately to the right of way line. Estimated tonnage and type of material required for this operation are shown in the surfacing plan.

The maximum grades shown are to be the limiting grades for all road approaches. Modifications of grades will be permitted where adherence to the grades as shown would cause damage to property or create other unsatisfactory conditions. Grades less than the maximum shown are to be used wherever feasible.

COLORADO
STATE HIGHWAY DEPARTMENT

STANDARD
SIDE APPROACH ROADS,
FLARING, CUT SLOPE TREATMENT
& WIDENING AT BRIDGES.

Designed by A.Z.
Made by G.R.S.
Checked by

Approved by R.E.L.
Date Sept. 25 1945

FLARING OF EARTH CUTS:


The backslopes at ends of all earth cuts shall be flattened and where necessary the ditch shall be widened gradually to discharge side ditch drainage away from the base of adjacent fill slopes in order to avoid erosion and to improve appearance. The transition of flattened backslopes and widened ditch shall be constructed in such a manner that a uniform appearance of slope and ditch results. Backslopes shall be flared to the approximate L distance shown in table below. Rock cuts shall not be flared.

NORMAL SLOPE	CUT H	DISTANCE L
1 To 1	24'	24'±
1.5 To 1	16'	24'±
2 To 1	12'	24'±
3 To 1	8'	24'±


CUT SLOPE TREATMENT IN EARTH CUTS:

The intersection of Cut Slopes with the existing ground shall be rounded in earth cuts, beginning 5 ft. outside the slope stake and extending 5 ft. down the cut slope. Where the cut slope is less than 5 ft., reduce each of the above widths of slope treatment to the actual slope distance. Quantities shall be included in "Unclassified Excavation."


CASE I



CASE II



PLAN OF FLARING IN EARTH CUTS




WIDENING AT BRIDGE APPROACHES:

Roadway Embankment at Bridge Approaches shall be so constructed that the finish point of the subgrade shoulder is a minimum of 2 ft. beyond the outside edge of bridge deck. Where widening of the section is necessary to achieve this result, it shall take place gradually over a distance of 300 ft. This is done to accommodate Guard Fence and/or Guard Posts at Bridge Approaches. (See additional requirements for Guard Fences below.)

WIDENING TO ACCOMMODATE GUARD FENCES:

At all locations on the project (except as provided above for bridge approaches) where guard fence is to be constructed the shoulders shall be widened 2 feet to provide additional lateral support for guard fence posts.





TYPICAL METHOD OF MARKING DETOUR (TRAFFIC PROHIBITED ON ROAD UNDER CONSTRUCTION)

STANDARD M-2-D





FED. ROAD DIST. NO.	STATE	SHEET NO.	TOTAL SHEETS
3	COLO.	17	

Rev. 9-10-46 Slow Signs R&R


TYPICAL METHOD OF MARKING HIGHWAY (TRAFFIC PERMITTED ON ROAD UNDER CONSTRUCTION)




DETAILS OF BARRICADES



POSITION OF SIGNS RELATIVE TO ROADBED & HAZARDS



DETAILS OF CONSTRUCTION SIGNS



GENERAL NOTES

ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS OF THE COLORADO STATE HIGHWAY DEPARTMENT APPLICABLE TO THE PROJECT. WHERE TRAFFIC IS MAINTAINED THROUGH OR OVER ANY PART OF THE PROJECT THE CONTRACTOR WILL BE REQUIRED TO MARK ALL HAZARDS WITHIN THE LIMITS OF THE PROJECT WITH WELL PAINTED, WELL MAINTAINED BARRICADES AND STANDARD CAUTION SIGNS, WARNING SIGNS, AND DIRECTIONAL TYPE SIGNS. BARRICADES AND SIGNS SHALL BE MOVED, ADDED TO, CHANGED OR REMOVED AS REQUIRED DURING THE PROGRESS OF CONSTRUCTION TO MEET CHANGING CONDITIONS.

THE CONTRACTOR SHALL FURNISH AND INSTALL THE FOLLOWING AS REQUIRED WITHIN THE LIMITS OF THE PROJECT:

1. ALL BARRICADES.
2. SLOW - ROAD UNDER CONSTRUCTION (CONTRACTOR'S NAME) SIGNS - MINIMUM 2.
3. STANDARD CAUTION, WARNING AND DIRECTIONAL TYPE SIGNS AS REQUIRED.
4. END OF CONSTRUCTION (CONTRACTOR'S NAME) SIGNS - MINIMUM 2.

FLARES OR TORCHES AS FOLLOWS:

A. TYPE I BARRICADES - MINIMUM 3 EACH.

B. TYPE II OR III BARRICADES - MINIMUM 1 EACH.

C. STANDARD CAUTION OR WARNING SIGNS - MINIMUM 1 EACH.

NOTE: FLARES OR TORCHES SHALL BE OF AN OIL BURNING TYPE APPROVED BY THE STATE OF COLORADO AND SHALL BE PLACED FROM 3 TO 8 FEET AHEAD OF THE SIGN OR OBJECT TO BE ILLUMINATED. IN ALL CASES FLARES OR TORCHES SHALL BE PLACED A SUFFICIENT DISTANCE AWAY, WITHIN THE ABOVE RANGE, TO AVOID DAMAGE TO FACE OF SIGN FROM SMOKE OR FLAME AND SHALL BE KEPT BURNING FROM SUNSET TO SUNRISE.

ALL LUMBER USED IN BARRICADES AND SIGNS SHALL BE SOUND, DURABLE MATERIAL AND SHALL BE KEPT WELL PAINTED WITH NEAT, UNIFORM LETTERS AND SYMBOLS CONFORMING TO STYLE SHOWN FOR THE VARIOUS SIGNS. UNEVEN OR SMEARED LETTERING WILL NOT BE PERMITTED.

WHERE TRAFFIC IS PROHIBITED FROM THE PROJECT, THE DETOUR WILL BE MARKED BY THE DEPARTMENT, EXCEPT THAT TYPE I BARRICADES, COMPLETE WITH NECESSARY ARROWS AND SIGNS, SHALL BE PROVIDED, ERECTED, PAINTED AND MAINTAINED BY THE CONTRACTOR AT BOTH ENDS OF THE PROJECT AND AT ALL INTERSECTING ROADS REQUIRED TO BE LEFT OPEN FOR CROSS TRAFFIC.

US AND/OR STATE ROUTE MARKERS DEEMED NECESSARY FOR GUIDANCE OF TRAFFIC OVER THE PROJECT OR FOR USE ON TYPE I BARRICADES WILL BE FURNISHED BY THE DEPARTMENT TO BE INSTALLED BY THE CONTRACTOR.

THE CONTRACTOR WILL BE RESPONSIBLE FOR ALL SIGNS FURNISHED HIM BY THE DEPARTMENT AND SHALL RETURN SAME UPON COMPLETION OF THE PROJECT. THE CONTRACTOR WILL BE REQUIRED TO REIMBURSE THE DEPARTMENT FOR ANY SIGNS FURNISHED HIM WHICH HAVE BECOME DAMAGED OR LOST DURING HIS OPERATIONS.

THE TYPICAL METHOD OF MARKING AS SHOWN ILLUSTRATES THE MINIMUM ACCEPTABLE SIGNING PROCEDURE. MODIFICATIONS AND ADDITIONAL REQUIREMENTS WILL BE DETERMINED BY LOCATION, TRAFFIC VOLUME AND OTHER PERTINENT CONDITIONS AFFECTING THE PUBLIC CONVENIENCE AND SAFETY.

ANY SPECIAL SIGNS DEEMED NECESSARY FOR THE GUIDANCE AND PROTECTION OF TRAFFIC OVER THE PROJECT OR DETOUR WILL BE FURNISHED AND INSTALLED BY THE DEPARTMENT.

ALL COSTS INCIDENTAL TO THE FOREGOING REQUIREMENTS WILL NOT BE PAID FOR AS A SEPARATE ITEM BUT SHALL BE INCLUDED IN THE ORIGINAL CONTRACT PRICES FOR THE PROJECT.

DETAILS OF REFLECTORIZED ARROW



For use on Type I Barricades at ends of project and/or inside of project where needed. Reflector buttons shall be Signal Service ALA 31 (white crystal) or suitable equivalent. Minimum thickness of lumber to be 1".

COLORADO
STATE HIGHWAY DEPARTMENT

STANDARD
ROADWAY CONSTRUCTION
TRAFFIC SIGNS

Designed by R.F.F.
Made by S.C.C.
Checked by

Approved by R.E.L.
Date: Sep. 25, 1945

PLAN
SHEET NO. 18
ALWAYS CHECK
FOR REVISIONS

PROFILE
SHEET NO. 18
ALWAYS CHECK
FOR REVISIONS

FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
3	COLO.	F 92(2)	18	

REV. BEGINNING & END OF PROJECT 7/27/47, E.E.O.




PLATE 1-PLAN-PROFILE
100% DESIGN
100% DESIGN